

AD-A107 412

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT
NATIONAL DAM SAFETY PROGRAM. LARCHWOOD LAKE DAM (INVENTORY NUMB--ETC(U)
AUG 81 H C FLAHERTY


F/G 13/13


DACW51-81-C-0006

NL

UNCLASSIFIED

1-3
AUG 81





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD A107412

SUSQUEHANNA RIVER BASIN

LEVEL II

LARCHWOOD LAKE DAM

OTSEGO COUNTY, NEW YORK
INVENTORY No. NY 727

PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

THIS COPY FURNISHED TO THE
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.



DTIC
ELECT
NOV 16 1981
S D D

APPROVED FOR PUBLIC RELEASE,
DISTRIBUTION UNLIMITED

NEW YORK DISTRICT, CORPS OF ENGINEERS
MAY 1981

81 11 13 079

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A107412	
4. TITLE (and Subtitle) Phase I Inspection Report Larchwood Lake Dam Susquehanna River Basin, Otsego County, N.Y. Inventory No. 727		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) HUGH C. FLAHERTY		6. PERFORMING ORG. REPORT NUMBER
		8. CONTRACT OR GRANT NUMBER(s) DACW51-81-C-0006
9. PERFORMING ORGANIZATION NAME AND ADDRESS Flaherty-Giavara Associates One Columbus Plaza New Haven, CT 06510		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 11
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		12. REPORT DATE 4 Aug 1981
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
15. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) 6 National Dam Safety Program. Larchwood Lake Dam (Inventory Number NY 727), Susquehanna River Basin, Otsego County, New York. Phase I Inspection Report,		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Larchwood Lake Dam Otsego County Susquehanna River Basin		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.		

Hydrologic/hydraulic analyses performed in accordance with the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams indicate that the principal spillway and the emergency spillway would pass 100 percent of the outflow from the Probable Maximum Flood (PMF) without overtopping the dam. Therefore, the combined spillway capacity is adjudged to be adequate.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
F	53 CP

DTIC
ELECTE
S NOV 16 1981 D
D

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LARCHWOOD LAKE DAM
INVENTORY NO. NY 727
SUSQUEHANNA RIVER BASIN
OTSEGO COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
ASSESSMENT	-
OVERVIEW PHOTOGRAPH	-
LOCATION MAP	i
1 - PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	3
2 - ENGINEERING DATA	6
2.1 GEOTECHNICAL DATA	6
2.2 DESIGN RECORDS	6
2.3 CONSTRUCTION RECORDS	7
2.4 OPERATION RECORDS	7
2.5 EVALUATION OF DATA	7
3 - VISUAL INSPECTION	8
3.1 FINDINGS	8
3.2 EVALUATION OF OBSERVATIONS	10
4 - OPERATION AND MAINTENANCE PROCEDURES	11
4.1 PROCEDURE	11
4.2 MAINTENANCE OF DAM	11
4.3 WARNING SYSTEM	11
4.4 EVALUATION	11

5 - HYDROLOGIC/HYDRAULIC	12
5.1 DRAINAGE AREA CHARACTERISTICS	12
5.2 ANALYSIS CRITERIA	12
5.3 SPILLWAY CAPACITY	12
5.4 RESERVOIR CAPACITY	14
5.5 FLOODS OF RECORD	14
5.6 OVERTOPPING POTENTIAL	14
5.7 EVALUATION	14
6 - STRUCTURAL STABILITY	16
6.1 EVALUATION OF STRUCTURAL STABILITY	16
7 - ASSESSMENT/RECOMMENDATIONS	17
7.1 ASSESSMENT	17
7.2 RECOMMENDED MEASURES	17

APPENDICES

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS
- E. REFERENCES
- F. DRAWINGS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Larchwood Lake Dam
State Located: New York
County: Otsego
Watershed: Susquehanna River Basin
Stream: Butts Corners Creek
Dates of Inspection: March 12 and 14, 1981

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies that need to be evaluated and remedied.

Hydrologic/hydraulic analyses performed in accordance with the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams indicate that the principal spillway and the emergency spillway would pass 100 percent of the outflow from the Probable Maximum Flood (PMF) without overtopping the dam. Therefore, the combined spillway capacity is adjudged to be adequate.

It is recommended that the following additional investigation be performed by a registered professional engineer engaged by the owner:

1. Determine to what extent the erosion due to high velocities in the emergency spillway will affect the stability of the channel bottom and left side slope as well as the dam embankment.

This investigation should be initiated within 6 months and completed within 18 months of the final approval date of this report.


In addition to any items required as a result of the additional investigation recommended above, the following remedial measures should be implemented within 12 months from the final approval date of this report:

1. Remove the slumped material from the bottom of the emergency spillway channel and restore the channel cross section and slope protection. There is potential for further slumping unless the cause is identified and the restoration includes provisions for slope drainage or other corrective measures.

2. Regrade the dam crest to remove the ruts and pockets and permit surface runoff without promoting concentrated flow. A gravel surface layer would improve trafficability and minimize rutting.
3. Cut the brush on the dam and the emergency spillway slopes and channel bottom every year to prevent their becoming overgrown. Equipment and procedures for this cutting should be such as to avoid damage to existing grass and weed cover on the slopes. Any slopes that become further scarred by runoff or traffic should be reseeded and mulched.
4. Repair the broken toe drain pipe and cut both pipes shorter to reduce the unsupported length and minimize the potential for additional damage.
5. Remove the tree stumps from the vicinity of the drop inlet structure.
6. Ensure the reservoir drain is operational.
7. Develop and implement a flood warning and emergency evacuation plan to alert the public in the event conditions occur which could result in failure of the dam.


Submitted by:

FLAHERTY GIAVARA ASSOCIATES, P.C.



Hugh C. Flaherty, P.E. & L.S.
Chairman of the Board
New York License No. 58508

Approved by:




Col. W. M. Smith, Jr.
New York District Engineer

Date:

3 Aug 81



PHOTO #1: Overview of
Larchwood Lake Dam
Inventory No. NY 727



LOCATION MAP

LARCHWOOD LAKE DAM
INVENTORY No. NY 727

SUSQUEHANNA RIVER BASIN
OTSEGO COUNTY
LAURENS, NEW YORK



0 2000 4000

SCALE IN FEET

FLAHERTY • GIAVARA ASSOCIATES, P.C.

NATIONAL DAM SAFETY PROGRAM
PHASE I INSPECTION REPORT
LARCHWOOD LAKE DAM
INVENTORY NO. NY 727
D.E.C. NO. 130C-3588
SUSQUEHANNA RIVER BASIN
OTSEGO COUNTY, NEW YORK

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367. Flaherty Giavara Associates, P.C. has been retained by the New York District to inspect and report on selected dams in the State of New York. Authorization and notice to proceed was issued to Flaherty Giavara Associates, P.C. under a letter of December 24, 1980 from W.M. Smith, Jr., Colonel, Corps of Engineers. Contract No. DACW 51-81-C-0006 has been assigned by the Corps of Engineers for this work.

b. Purpose

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to life and property and recommend remedial measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

Larchwood Lake Dam consists of an earthen embankment with a concrete pipe principal spillway under the left central portion of the embankment and a sparsely vegetated emergency spillway channel cut into the right abutment. Plans, profiles and sections prepared for the project by the U.S. Department of Agriculture, Soil Conservation Service (SCS), are included on drawings in Appendix F.

The dam embankment is approximately 260 feet long and 36 feet high and has an upstream slope of 3 horizontal to 1 vertical and a downstream slope of 2.5 to 1. The crest of the dam is 14 feet in width and its elevation varies from 114.1 to 115.4 (Assumed Datum). There is a 10 foot wide berm at the toe of the upstream slope just below

normal pond level. The embankment has a cross section primarily of compacted glacial till and a 12 foot wide cutoff of the same material extending 4 to 5 feet below the original ground surface. Sparse grass cover provides erosion protection for the upstream slope. Riprap is provided around the principal spillway outlet.

The embankment has an internal drain constructed in pervious fill located near the downstream toe of slope. Two 8 inch diameter perforated bituminous-coated corrugated metal pipes (BCCMP) are embedded in the pervious fill to drain the embankment and they discharge into the stilling basin at both sides of the principal spillway outlet.

The principal spillway is a drop inlet structure consisting of a single stage reinforced concrete riser, a 30 inch diameter prestressed concrete cylinder pipe (PCCP) and a stilling basin at the outlet of the conduit.

The emergency spillway is a curved 85 foot wide, trapezoidal-shaped channel with 3 to 1 side slopes cut into earth at the right abutment. It is about 420 feet long, extending below the dam in a cut section. Both channel side slopes have a cover of broken shaley rock in random sizes ranging up to about 6 inches. The emergency spillway channel bottom slopes gently downward both upstream and downstream from a 50 foot wide level section (the spillway crest) that is in the vicinity of the right side of the dam crest. Approximately 150 feet of the left channel slope is formed by a spur dike which has a 12 foot crest that varies in elevation from approximately 110.4 to 114.1 (Assumed Datum). The discharge channel drops off steeply into the natural streambed at the downstream end. The channel bottom and side slopes of the emergency spillway and the slopes and crest of the spur dike are sparsely vegetated.

b. Location

The Larchwood Lake Dam is located off an unimproved road approximately 1.3 miles northwest of Butts Corners in the Town of Laurens, New York. The dam is located at latitude north 42°-33.0' and longitude west 75°-10.0' on the U.S. Geological Survey 7.5 minute series topographic map "Morris, New York". The Location Map on page i indicates where the dam is situated.

c. Size Classification

The maximum height of the dam is 36 feet and the maximum storage capacity at the top of dam is 1100 acre-feet. Therefore, Larchwood Lake Dam is classified as an "Intermediate" dam as defined by the Recommended Guidelines for

Safety Inspection of Dams.

d. Hazard Classification

There are approximately 4 dwellings and three roads within the dam failure flood hazard area. Therefore, the dam is in the "High" hazard category as defined by the Recommended Guidelines for Safety Inspection of Dams.

e. Ownership

The dam is owned by Larchwood Lake, Inc. The address and telephone number of the owner is as follows:

Owner

Contact: Larchwood Lake, Inc.
c/o Frank Getman
P.O. Box 613
Oneonta, New York 13820

Telephone: (607) 432-3530

f. Purpose

The primary purpose of this dam is to maintain the water level of the lake for recreational use.

g. Design and Construction History

The dam was designed by the Soil Conservation Service (SCS), of the U.S. Department of Agriculture (USDA) in 1966 and 1969. It was constructed in 1969 by Everett Van De Bogart of Oneonta, New York. No major post construction modifications have been made to the dam.

h. Normal Operating Procedure

The riser structure is always open; therefore, the water level is maintained at the elevation of the crest of the intake weir for normal flows. There are no regular operating procedures.

1.3 PERTINENT DATA

a. Drainage Area (Square Miles)

1.15

b. Discharge at Dam Site (CFS)

- Top of Dam	3071
- Crest of Emergency Spillway	108
- Crest of Principal Spillway	8
- Reservoir Drain Inlet	-

c. Elevations (Assumed Datum)

- Top of Dam	114.1
- Design High Water Level	111.2
- Crest of Emergency Spillway	108.6
- Crest of Principal Spillway	102.0
- Reservoir Drain Inlet	87.8

d. Reservoir Surface Area (Acres)

- Top of Dam	82.9
- Design High Water Level	74.6
- Crest of Emergency Spillway	66.9
- Crest of Principal Spillway	47.2

e. Storage (Acre-Feet)

- Top of Dam	1100
- Design High Water Level	861
- Crest of Emergency Spillway	675
- Crest of Principal Spillway	298

f. Dam

- Type: Homogeneous compacted glacial till with a glacial till cutoff	
- Crest Length (Feet)	260
- Upstream Slope (H:V)	3:1
- Downstream Slope (H:V)	2.5:1
- Crest Width (Feet)	14

g. Emergency Spillway

- Type: Excavated earthen channel; left bank is part of spur dike	
- Length (Feet)	420
- Bottom Width (Feet)	85
- Side Slopes (H:V)	3:1
- Channel Bottom Slopes (Feet/Foot)	
upstream	0.0200
downstream	0.0285
- Control: None	

h. Principal Spillway

- Type: Drop inlet structure consist- ing of a single stage rein- forced concrete riser, a 30 inch diameter prestressed con- crete cylinder pipe (120 feet long) and a stilling basin at	
---	--

the outlet end of the conduit

- Control: None

i. Reservoir Drain

- Type: 12 inch diameter asbestos cement pipe (39 feet long) having a trash rack and a reinforced concrete pond drain inlet and draining into the reinforced concrete riser

- Control: 12 inch flat frame slide gate located at the inlet to the reinforced concrete riser

j. Toe Drain

- Type: Two 8 inch diameter perforated bituminous-coated corrugated metal pipes in pervious fill

- Control: None

SECTION 2 - ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Larchwood Lake Dam is located in the Allegheny Plateau physiographic province of New York State.

The topography in the area ranges from an elevation of 1100 feet at the Susquehanna River to about 1800 feet on the summits of the hills. Glacial action has rounded the tops of the summits in the Allegheny Plateau and has deeply scoured the north-south valleys, such as the valley of Butternut Creek, west of the site. The lesser valley in which the dam is located was only moderately scoured by glacial erosion.

The underlying bedrock is of the Unadilla Formation and is Upper Devonian in age. It is a shallow water deposit made up of coarse silty shales and finely laminated siltstones deposited in the Catskill Delta as a consequence of mountain building that occurred to the east and south-east.

Above the bedrock the valley bottom and slopes are mantled by a heterogeneous mixture of clay, silt, sand and rock fragments. This soil is known as glacial till, and was deposited as the glacial ice melted back past the site.

b. Subsurface Investigations

Sixteen test pits were excavated for the project, with most or all being in the area of the dam and the emergency spillway. All of the pits apparently encountered low permeability glacial till at a relatively shallow depth, and terminated in dense glacial till at depths of 5 to 12 feet without reaching bedrock. Several test pits in the lower part of the valley revealed moderately permeable alluvium or colluvium above the glacial till at shallow depths ranging up to 4 feet. Logs of test holes are included on sheet 14 of the drawings in Appendix F.

2.2 DESIGN RECORDS

This dam was designed by the SCS in 1966 and 1969. As part of the design process, design calculations, a preliminary geologic investigation and soils testing were completed for the site. This data is included in Appendix D.

2.3 CONSTRUCTION RECORDS

This dam was constructed in 1969 by Everett Van De Bogart of Oneonta, New York. The contract drawings which were prepared by the SCS are included in Appendix F. No other construction records were available.

2.4 OPERATION RECORDS

There were no operation records available for this dam.

2.5 EVALUATION OF DATA

The data presented herein was obtained primarily from the SCS office located in Syracuse, New York and also from the files of the New York State Department of Environmental Conservation (DEC). This information appears to be reliable and adequate for the purposes of a Phase I Inspection Report.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspections of the Larchwood Lake Dam were conducted on March 12 and 14, 1981. The weather was overcast and the temperature was 35+°F. At the time of these inspections, there were patches of snow on the ground and water was flowing in the principal spillway outlet pipe (See Photo No. 16).

b. Dam

The earthfill embankment of the dam is generally in satisfactory condition. There was no visible evidence of lateral movement, significant seepage, major settlement or erosion, or other serious defects.

The following specific items were noted:

1. The crest of the dam embankment is rutted and somewhat irregular with ponded water (and ice) at several locations. The depressions are about 6 inches below the general level of the crest (See Photo No. 3).
2. The dam embankment slopes have a sparse cover of grass, weeds and occasional brush. Numerous fragments of shale were exposed on the upstream slope and may have been intended as a protective cover. Bare patches of soil are evident on the upper part of the downstream slope, but there has not been significant erosion (See Photos No. 4, 5, 6, 7, and 8).
3. There is wet ground and slight seepage at the intersection of the upstream slope with the left abutment. The source of the seepage appears to be ponded surface runoff at the end of the crest.
4. The discharge pipe of the left toe drain is broken off at the surface of the riprap. Neither drain was flowing (See Photo No. 15).

c. Principal Spillway

1. Riser Structure

The reinforced concrete riser structure with a drop inlet is in good condition. The inlet weir has a trash rack attached to it and is largely free from debris. However, four or five tree stumps remain from the construction of the dam and should be re-

moved. The gate stem for the reservoir drain was very rusty and was not operated during the inspection (See Photo No. 12). The riprap in place at the toe of the upstream embankment adjacent to the riser structure is in good condition with no bare spots observed (See Photo No. 13).

2. Principal Spillway Conduit

The 30 inch diameter prestressed concrete cylinder pipe (PCCP) is in excellent condition where visible (See Photo No. 16).

3. Principal Spillway Outlet

The 30 inch diameter conduit has a projecting end and discharges into a riprap stilling basin with a 6 foot drop. The cast-in-place concrete cradle supporting the cantilevered outlet pipe is in good condition. The riprap which surrounds the discharge pipe, its cradle and the toe drains appeared to be stable (See Photo No. 16). The stilling basin is in good condition having no major deterioration of the riprap lining (See Photo No. 14).

4. Principal Spillway Discharge Channel

The gravel-lined channel has an average width of 6 feet, a flow depth of 8 inches and narrows slightly in the downstream direction as it flows through a wooded area (See Photo No. 17).

d. Emergency Spillway

The dam has an 85 foot wide, trapezoidal-shaped, earthen spillway excavated into the right abutment. The approach channel, level crest, and discharge channel all have a thin, sparse grass cover and are in fair condition (See Photo No. 9).

The discharge channel is separated from the dam embankment by an earthen spur dike which is in good condition (See Photo No. 10).

The following specific items were noted:

1. Portions of the right cut slope downstream from the spillway crest, have sloughed about 15 feet out onto the channel bottom (See Photo No. 11).
2. There are scattered minor growths of brush and weeds among the rocks on the emergency spillway channel side slopes.

3. The bottom of the emergency spillway channel is locally irregular, and also has a sparse growth of grass, weeds, and low brush (See Photo No. 9).

e. Downstream Channel

The natural channel downstream of the dam site has a width of 10 to 15 feet. The streambed material consists of sand and fine to coarse gravel.

f. Reservoir - Storage Pool Area

The floodwater storage area is bordered by moderately sloping woodlands. There is no significant probability of landslides into the storage pool affecting the safety of the dam (See Photo No. 2). Sedimentation is not presently a safety factor because of the low normal pool level.

3.2 EVALUATION OF OBSERVATIONS

The visual inspections revealed some deficiencies. The following observations were made:

- a. Portions of the right side slope of the emergency spillway downstream from the crest have sloughed about 15 feet out onto the channel bottom.
- b. The crest of the dam embankment was rutted and somewhat irregular.
- c. The dam embankment slopes and emergency spillway channel bottom and side slopes have a sparse cover of grass, weeds and occasional brush.
- d. The outlet to the left toe drain of the embankment has broken off at its emergence from the slope.
- e. There are four or five tree stumps around the drop inlet structure.
- f. The gate stem used to operate the reservoir drain was very rusty.

SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

The normal water surface level is maintained by the crest of the intake weir in the riser structure at elevation 102.0 (Assumed Datum). No operational procedures are in effect at this time.

4.2 MAINTENANCE OF DAM

There was no evidence of any mowing, reservoir drain operation, or any other maintenance operations at the Larchwood Lake Dam.

4.3 WARNING SYSTEM

No warning system is presently in effect.

4.4 EVALUATION

Presently, there are none in effect; therefore, the operation and maintenance procedures for this dam are inadequate. Consequently, regular operation and maintenance procedures should be implemented.

SECTION 5 - HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

The dam is located in Laurens on Butts Corners Creek, 9500+ feet upstream of Wharton Creek. Butts Corners Creek joins Wharton Creek near Butts Corners, approximately five miles upstream of Otego Creek at West Oneonta, New York.

The watershed (shown on the Watershed Map on Page C-5 in Appendix C) consists of 735 acres (1.15 square miles) of rolling to hilly uplands with typical slopes of 5 to 10 percent. Land within the watershed is largely undeveloped with extensive open fields and woodlands. There are no significant waterbodies or wetlands located upstream of the dam.

The watercourse upon which the dam is located is a small perennial stream with a typical flow width of 10 feet and a typical flow depth of 8 inches.

5.2 ANALYSIS CRITERIA

The purpose of the hydrologic/hydraulic analysis is to evaluate the spillway capacity and the potential for overtopping. The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers' HEC-1 Computer Model - Dam Safety Version. The procedure included determining the Probable Maximum Flood (PMF) runoff from the watershed and routing the inflow hydrograph through the impoundment to determine the outflow hydrograph. The unit hydrograph was defined by the Snyder Synthetic Unit Hydrograph method, and the Modified Puls routing procedure was incorporated.

The initial rainfall loss was assumed to be 1.0 inches, and the uniform rainfall loss was assumed to be 0.1 inches per hour. In accordance with recommended guidelines of the Corps of Engineers, the Probable Maximum Precipitation (PMP) was 19.7 inches (24 hour duration, 200 square mile area).

The analysis was conducted for both the full PMF and for several fractional PMF conditions. The PMF inflow of 2970 CFS was routed through the reservoir and the peak outflow was determined to be 2173 CFS.

5.3 SPILLWAY CAPACITY

The total outlet capacity is the sum of discharges from the principal spillway and the emergency spillway.

The principal spillway consists of a riser structure with a drop inlet, a conduit and a stilling basin. The crest elevation of the drop inlet is 102.0 feet (from SCS design data)

at the normal pool elevation and the invert elevation of the principal spillway conduit (30" PCCP) is 86.75 at its inlet and 85.75 at its outlet into the stilling basin. A reservoir drain (12 inch diameter asbestos cement pipe) is located at the upstream toe of slope at an elevation of 87.75. Flow is conveyed through the 12 inch reservoir drain to the riser structure and then through the 30 inch conduit into the stilling basin. Flow through the reservoir drain is controlled at the riser structure by a 12 inch diameter flat frame slide gate. The flow capacity was evaluated by assuming that its capacity was controlled by the inlet, which acts as an orifice during periods of high flow.

The emergency spillway is an 85 foot wide trapezoidal-shaped, sparsely vegetated channel. The SCS design information indicates the emergency spillway was designed to be used only by a flood event with an average return frequency of more than 100 years.

The stage discharge curve for the combined principal and emergency spillways was obtained from the Soil Conservation Service for the stages tabulated below:

Stage (Feet)	Discharge Capacity (CFS)	Element of Structure
102.0	0	Normal Water Level
103.0	40	--
104.0	96	--
105.0	99	--
106.0	102	--
107.0	104	--
108.0	107	--
108.6	108	Emergency Spillway Crest
109.0	149	--
110.1	416	--
111.1	814	--
111.2	869	Design High Water Level
112.1	1397	--
113.1	2179	--
114.1	3071	Top of Dam

The total spillway capacity at the top of dam is 3071 CFS.

The principal spillway can pass the peak outflow from a flood equal to approximately 34 percent of the PMF before use of the emergency spillway would be required.

The energy grade line of the PMF discharge would be 4.4 feet above the crest of the emergency spillway. The average flow velocity in the emergency spillway discharge channel would be

10.5 feet per second (FPS), which may cause erosion of the sparsely vegetated channel.

5.4 RESERVOIR CAPACITY

The storage capacity of the reservoir was obtained from the Soil Conservation Service, as indicated below:

<u>Stage (Feet)</u>	<u>Storage (Acre-Feet)</u>	<u>Storage (Inches of Runoff)</u>
88.0	0.2	0.00
90.0	4	0.07
92.0	18	0.29
94.0	42	0.69
96.0	82	1.34
98.0	139	2.27
100.0	211	3.44
102.0	298	4.86
104.0	399	6.51
106.0	512	8.36
108.0	636	10.38
110.0	772	12.60
112.0	920	15.02
114.0	1080	17.63

5.5 FLOODS OF RECORD

No records of floods were available for this dam.

5.6 OVERTOPPING POTENTIAL

The results of the HEC-1 DB computer analysis indicate that the crest of the dam is not overtopped by the PMF event. The PMF discharge rate of 2173 cubic feet per second (CFS) would occur at a peak flood stage of 113.0 feet, which is 1.1 feet below the crest of the dam.

The results of the analysis are tabulated below:

<u>Flood Condition</u>	<u>Peak Inflow (CFS)</u>	<u>Peak Outflow (CFS)</u>	<u>Maximum Stage Elevation (Assumed Datum)</u>
0.5 PMF	1485	517	110.4
1.0 PMF	2970	2173	113.0

5.7 EVALUATION

Using the Corps of Engineers' screening criteria for the initial review of spillway adequacy, it has been determined that the dam would not be overtopped by either the full Probable

Maximum Flood (PMF) or one half the PMF. Approximately 1.1 feet of freeboard would exist between the PMF maximum water level and the crest of the dam. Therefore, the spillway is adjudged to be adequate.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

There was no visible evidence of major settlement, lateral movement or other signs of overall structural instability of the dam during the site examinations. However, the pool level was approximately 12 feet below the top of the dam at the time, with the result that the forces tending to cause instability were much lower than design levels. Based on the conditions that were observed, there is no reason to question the static structural stability of the dam.

b. Design and Construction Data

Although they are not labelled "As-Built", the Soil Conservation Service record drawings for the Larchwood Lake Dam (see Appendix F) show a configuration for the dam embankment and emergency spillway that generally corresponds to the conditions observed during the visual examinations on March 12 and 14, 1981. It is noted that the "Riser Revisions" on Sheet 8A, dated September 1969, have been incorporated in the construction of the dam.

There is no construction data to confirm the actual physical properties and configuration of the earthfill in the embankments. However, the dam proportions are considered to be reasonable for the soils that were available at the site and the dam would be expected to have adequate safety margins with respect to stability under static loading conditions.

c. Seismic Stability

The Larchwood Lake Dam is located in Seismic Zone 1, and in accordance with recommended Phase I guidelines does not require seismic analysis.

SECTION 7 - ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Condition

On the basis of the visual examinations, the Larchwood Lake Dam is considered to be in fair condition. There were no signs of impending structural failure or other conditions which would warrant urgent remedial action; however, a number of deficiencies were noted.

b. Adequacy of Information

The evaluation of this dam is based primarily on visual examinations, reference to available SCS plans, approximate hydraulic and hydrologic computations, and application of engineering judgement. The visual examination was somewhat hampered by low pool level and weather conditions; however, the available information that was obtained is adequate for the purposes of a Phase I assessment.

c. Need for Additional Investigations

It is recommended that the following additional investigation be performed by a registered professional engineer engaged by the owner:

1. Determine to what extent the erosion due to high velocities in the emergency spillway will affect the stability of the channel bottom and the left side slope well as the dam embankment.

d. Urgency

The additional investigation recommended in Section 7.1c should be initiated within 6 months and appropriate remedial measures completed within 18 months of the final approval date of this report. The recommended measures presented in Section 7.2 should be completed within 12 months of the final approval.

7.2 RECOMMENDED MEASURES

Due to the fact the dam is generally in fair condition, it is considered important that the following items be accomplished in addition to any items required as a result of the additional investigation recommended in Section 7.1c:

- a. Remove the slumped material from the bottom of the emergency spillway channel and restore the channel cross section and slope protection. There is potential for fur-

ther slumping unless the cause is identified and the restoration includes provisions for slope drainage or other corrective measures.

- b. Regrade the dam crest to remove the ruts and pockets and permit surface runoff without promoting concentrated flow. A gravel surface layer would improve trafficability and minimize rutting.
- c. Cut the brush on the dam and emergency spillway slopes and channel bottom every year to prevent their becoming overgrown. Equipment and procedures for this cutting should be such as to avoid damage to existing grass and weed cover on the slopes. Any slopes that become further scarred by runoff or traffic should be reseeded and mulched.
- d. Repair the broken toe drain pipe and cut both pipes shorter to reduce the unsupported length and minimize the potential for additional damage.
- e. Remove the tree stumps from the vicinity of the riser structure.
- f. Ensure the reservoir drain is operational.
- g. Develop and implement a flood warning and emergency evacuation plan which would be implemented to alert the public in the event conditions occur which could result in the failure of the dam.

I
I

APPENDIX A
PHOTOGRAPHS




PHOTO LOCATION MAP

LARCHWOOD LAKE DAM
 INVENTORY No. NY 727
 OTSEGO COUNTY
 LAURENS, NEW YORK

LEGEND

Number refers to caption.
 Arrow indicates direction
 of photograph.





PHOTO #2: Overview of impoundment



PHOTO #3: Crest of dam looking toward
left abutment



PHOTO #4: Overview of upstream face of dam



PHOTO #5: Overview of downstream face of dam




PHOTO #6: Upstream face of dam



PHOTO #7: Downstream face of dam looking toward right abutment



PHOTO #8: Downstream face of dam looking toward left abutment



PHOTO #9: Emergency spillway looking upstream



PHOTO #10: Crest of spur dike



PHOTO #11: Sloughing of right side slope
of emergency spillway




PHOTO #12: Principal spillway drop inlet structure



PHOTO #13: Riprap slope protection near drop inlet structure



PHOTO #14: Riprap-lined stilling basin



PHOTO #15: Principal spillway outlet works;
30" prestressed concrete cylinder
pipe (PCCP) and toe drains
(one broken)



PHOTO #16: Closeup of outlet works (toe drain not flowing)



PHOTO #17: Downstream channel conditions

APPENDIX B
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Larchwood Lake Dam
Fed. I.D. # NY 727 DEC Dam No. 130C-3588
River Basin Susquehanna
Location: Town Laurens County Otsego
Stream Name Butts Corners Creek
Tributary of Wharton Creek
Latitude (N) 42°-33.0' Longitude (W) 75°-10.0'
Type of Dam Earthen embankment
Hazard Category High
Date(s) of Inspection March 12 and 14, 1981
Weather Conditions Overcast, 35±° F.
Reservoir Level at Time of Inspection Elevation 102.1 (Assumed Datum)

- b. Inspection Personnel R.C. Smith, T.L. Ward and R.A. Criscuolo of Flaherty Giavara Associates, P.C.; P.L. LeCount and J.J. Rixner of Haley & Aldrich, Inc.; E. Thomas of Salmon Associates; G.L. Page of the Soil Conservation Service (USDA)
c. Persons Contacted (Including Address & Phone No.)

Gary L. Page	Donald W. Lake Jr.
Binghamton Watershed Office	Soil Conservation Service
Soil Conservation Service	771 Federal Building
P.O. Box 1255	100 South Clinton Street
Broome County Airport	Syracuse, New York 13260
Binghamton, New York 13902	(315) 423-5505
(607) 773-2751	

d. History:

Date Constructed 1969 Date(s) Reconstructed Never

Designer Soil Conservation Service
Constructed By Everett Van De Bogart
Owner Larchwood Lake, Inc.

2) Embankment

a. Characteristics

- (1) Embankment Material Very firm fragipan and till; silty gravel
- (2) Cutoff Type Compacted glacial till
- (3) Impervious Core None
- (4) Internal Drainage System Two 8 inch perforated BCCMP toe drains on either side of the principal spillway outlet; no flow in either drain
- (5) Miscellaneous No comments

b. Crest

- (1) Vertical Alignment Excellent; slightly crowned at the center of the dam
- (2) Horizontal Alignment Excellent; substantially straight
- (3) Surface Cracks None evident
- (4) Miscellaneous Wheel rutting and low spots

c. Upstream Slope

- (1) Slope (Estimate - V:H) 1:3
- (2) Undesirable Growth or Debris, Animal Burrows None observed
- (3) Sloughing, Subsidence or Depressions None apparent

(4) Slope Protection Sparse grass and weeds; occasional brush; numerous
pieces of shale exposed; riprap around concrete riser appears satisfactory

(5) Surface Cracks or Movement at Toe None evident

d. Downstream Slope

(1) Slope (Estimate - V:H) 1:2.5

(2) Undesirable Growth or Debris, Animal Burrows None observed

(3) Sloughing, Subsidence, or Depressions None evident; however, bare soil
exposed in patches on upper portion

(4) Surface Cracks or Movement at Toe None evident

(5) Seepage None observed

(6) External Drainage System (Ditches, Trenches, Blanket) None observed

(7) Condition Around Outlet Structure Riprap surrounds the outlets of the
principal spillway and the toe drains but has fallen away from the toe drains
causing the left one to break off at the slope

(8) Seepage Beyond Toe None observed

e. Abutments - Embankment Contact

Good condition

(1) Erosion at Contact None evident

(2) Seepage Along Contact None observed

3) Drainage System

a. Description of System Drop inlet structure consisting of a reinforced concrete riser, a 30 inch diameter conduit and a stilling basin

b. Condition of System Excellent

c. Discharge from Drainage System Riprap-lined stilling basin

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Peizometers, Etc.)

None observed

5) Reservoir

- a. Slopes Moderately sloping woodlands
- b. Sedimentation No apparent problems
- c. Unusual Conditions Which Affect Dam Low normal pool level

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Approximately 4 dwellings and 3 roads are within the dam failure flood hazard area
- b. Seepage, Unusual Growth None observed
- c. Evidence of Movement Beyond Toe of Dam None observed
- d. Condition of Downstream Channel Good; no aggradation or degradation

7) Spillway(s) (Including Discharge Conveyance Channel)

Principal spillway, emergency spillway and discharge conveyance channel

- a. General Principal spillway and discharge conveyance channel handle normal flows, while the emergency spillway conveys flood events with average return frequencies greater than 100 years
- b. Condition of Principal Spillway Good; however, debris has collected around old stumps in front of the trash rack and could hinder flow over the weir

c. Condition of Emergency Spillway Fair; a section of the right side slope has
sloughed out about 15 feet onto the channel bottom

d. Condition of Discharge Conveyance Channel Good; the bed is gravel-lined and the
banks appear stable

8) Reservoir Drain/Outlet

Type: Pipe Two Conduit _____ Other _____

Material: Concrete X Metal _____ Other Asbestos cement

Size: Conc: 30 in., Asbestos cement: 12 in. Length 120 feet and 39 feet

Invert Elevations: Entrance 87.75 Exit 85.75

Physical Condition (Describe): _____ Unobservable X

Material: Prestressed concrete cylinder and asbestos cement

Joints: Rubber/Steel and Rubber Alignment Straight

Structural Integrity: Excellent

Hydraulic Capability: Good

Means of Control: Gate Flat Frame
Slide Gate Valve _____ Uncontrolled _____

Operation: Operable _____ Inoperable X Uncontrolled _____

Present Condition (Describe): Each pipe is in excellent condition; however, the
slide gate appears to be rusted shut in the closed position

9) Structural

a. Concrete Surfaces Good condition

b. Structural Cracking None observed

c. Movement - Horizontal & Vertical Alignment (Settlement) None evident

d. Junctions with Abutments or Embankments Not applicable

e. Drains - Foundation, Joint, Face Not applicable

f. Water Passages, Conduits, Sluices Not applicable

g. Seepage or Leakage None observed

- h. Joints - Construction, etc. Not applicable
- i. Foundation Not applicable
- j. Abutments Not applicable
- k. Control Gates 12 inch flat frame slide gate on the reservoir drain at its inlet to the reinforced concrete riser
- l. Approach & Outlet Channels Not applicable
- m. Energy Dissipators (Plunge Pool, etc.) Riprap-lined stilling basin at the principal spillway outlet
- n. Intake Structures Reinforced concrete riser with overflow weir in good condition
- o. Stability No evidence of structural instability
- p. Miscellaneous No comments

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition None

This image shows a single sheet of white paper with horizontal blue or grey ruling lines. The lines are evenly spaced and run across the width of the page. There are approximately 20 lines visible. The paper appears to be a standard notebook or ledger page.

APPENDIX C

HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS

**CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA**

AREA-CAPACITY DATA:

	<u>Elevation (ft.)</u>	<u>Surface Area (acres)</u>	<u>Storage Capacity (acre-ft.)</u>
1) Top of Dam	<u>114.1</u>	<u>82.9</u>	<u>1090</u>
2) Design High Water (Max. Design Pool)	<u>111.2</u>	<u>74.6</u>	<u>861</u>
3) Emergency Spillway Crest	<u>108.6</u>	<u>66.9</u>	<u>675</u>
4) Pool Level with Flashboards	<u>---</u>	<u>---</u>	<u>---</u>
5) Principal Spillway Crest	<u>102.0</u>	<u>47.2</u>	<u>298</u>

DISCHARGES:

	<u>Volume (cfs)</u>
1) Average Daily	<u>Unknown</u>
2) Emergency Spillway @ Maximum High Water (Top of Dam)	<u>2950</u>
3) Emergency Spillway @ Design High Water	<u>754</u>
4) Principal Spillway @ Emergency Spillway Crest	<u>108</u>
5) Low Level Outlet @ Principal Spillway Crest	<u>8</u>
6) Total (of all facilities) @ Maximum High Water	<u>3071</u>
7) Maximum Known Flood	<u>Unknown</u>
8) At Time of Inspection	<u>1+</u>

CREST:

ELEVATION: 114.1

Type Vegetated earthen embankment

Width 14 feet

Length 260 feet

Spillover Sparsely vegetated emergency spillway

Location Right abutment

SPILLWAY:

PRINCIPAL		EMERGENCY
102.0	Elevation	108.6
Drop inlet structure	Type	Earth excavated
13 feet, 4 inches	Width	85 feet
<u>Type of Control</u>		
Weir	Uncontrolled	Weir
--	Controlled	--
--	Type: (Flashboards; gate)	--
One	Number	One
30 inch/120 feet	Size/Length	85 feet/420 feet
Concrete	Invert Material	Sparsely vegetated cover on earth
Continuously	Anticipated Length of Operating Service	11.84 hours
Not applicable	Chute Length	220 feet
1.0 feet	Height Between Spillway Crest & Approach Channel Invert (Weir Flow)	Slope = 0.0200 on the approach channel

Type: _____

Location: _____

Records:

Date Unknown

Max. Reading Unknown

FLOOD WATER CONTROL SYSTEM:

Warning System None in effect

Method of Controlled Releases (mechanisms) Manually controlled slide gate to
drain the impoundment

DRAINAGE AREA: 735 acres = 1.15 square miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type Rural, agriculture

Terrain - Relief Moderate slopes

Surface - Soil Glacial till

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface conditions)

Moderate due to rolling uplands

Potential Sedimentation problem areas (natural or man-made; present or future)

None

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the reservoir
perimeter:


Location: Spur dike at the right end of the dam embankment

Elevation: Approximately 110.4 to 114.1 (Assumed Datum)

Reservoir:

Length @ Maximum Pool 4600± feet = 0.9 miles (Miles)

Length of Shoreline (@ Spillway Crest) 10,600± feet = 2.0 miles (Miles)



WATERSHED MAP

LARCHWOOD LAKE DAM

INVENTORY No. NY 727

SUSQUEHANNA RIVER BASIN

OTSEGO COUNTY

LAURENS, NEW YORK



0 2000 4000

SCALE IN FEET

FLAHERTY • GIAVARA ASSOCIATES, P.C.

CALCULATIONS



WATERSHED DATA FOR HEC I SNYDER HYDROGRAPH

1) TIME TO PEAK

$$L = 19,000 \text{ FT} = 1.89 \text{ miles}$$

$$L_c = 4,000 \text{ FT} = 0.76 \text{ miles}$$

$$C_t = 2.0 \text{ for average slopes}$$

$$\begin{aligned} T_p &= C_t (L + L_c)^{0.3} \\ &= 2.0 (1.89 + 0.76)^{0.3} \\ &= 2.23 \end{aligned}$$

$$t_r = \frac{T_p}{5.5} = \frac{2.23}{5.5} = 0.41 \quad \text{USE } t_r = 0.5$$

$$\begin{aligned} t_{pR} &= T_p + 0.25(t_R - t_r) \\ &= 2.23 + 0.25(0.5 - 0.41) \\ &= 2.25 \text{ Hours} \end{aligned}$$

2) SNYDER'S Peaking coefficient (CP) = 0.63 for Highlands

3) % Impervious

$$\begin{aligned} \text{Roads } 7000' \times 25' &= 175,000 \text{ ft}^2 \\ \text{Houses } 2 \times 1000' &= \frac{2000 \text{ ft}^2}{177,000 \text{ ft}^2} \end{aligned}$$

$$177,000 \text{ ft}^2 = 4 \text{ acres}$$

$$\frac{4 \text{ acres}}{735 \text{ acres}} = 0.5\% \text{ of watershed}$$

4) WATERSHED AREA

$$735 \text{ acres} / 640 = 1.15 \text{ square miles}$$

PROJECT CORPS Linc
NY 727



FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA NEW HAVEN CONN 06510/203/789-1200

SHEET NO. 2 OF 6
BY RAC DATE 3-21-81
CHK'D. BY TLW DATE 4-28-81

5) Rainfall Data (from Hydrometeorological Report
No. 33)

24 Hour Duration PMP = 19.7 inches
For 200 square miles

<u>Duration Hrs</u>	<u>Adj Factor %</u>
6	111
12	122
24	133
48	143

PROJECT COEPS DAMS
NHPP



FLAHERTY-GIAVARA ASSOCIATES
 ENVIRONMENTAL DESIGN CONSULTANTS
 ONE COLUMBUS PLAZA, NEW HAVEN, CONN 06510/203/789-1200

SHEET NO. 5 OF 6
 BY PLC DATE 3-28-81
 CHK'D BY TLW DATE 4-28-81

PRINCIPAL & EMERGENCY DISCHARGE

STAGE DISCHARGE DATA - (FROM GCD)

<u>STAGE, FT</u>	<u>PRINCIPAL HEAD, FT</u>	<u>EMERGENCY HEAD, FT</u>	<u>DISCHARGE CFS</u>
102.0	0	-	0
102.5	0.5	-	14.3
103.0	1.0	-	40.3
103.5	1.5	-	74.2
103.8	1.8	-	97.5
103.9	1.9	-	105.6
104.0	2.0	-	106.8
104.3	2.3	-	107.7
108.6	6.6	0	1084
109.0	7.0	0.4	149.3
109.1	7.6	1.0	2307
110.1	8.7	1.5	416.1
110.6	9.1	2.0	593.2
111.1	9.7	2.5	814.2
112	10.2	2.6	907.7
112.6	10.6	3.0	1027.2
112.7	10.7	3.5	1342.5
113.1	11.1	4.5	2170.1
114	12.1	5.5	3671.1

PROJECT CORP DAM
NY 727




FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA, NEW HAVEN, CONN 06510/203/786-1280

SHEET NO. 4 OF 6
BY RAC DATE 3-23-81
CHK'D BY TLW DATE 4-28-81

STAGE - DISCHARGE CURVE

PRINCIPAL & EMERGENCY SPILLWAYS




EMERGENCY SPILLWAY DISCHARGE CHANNEL

$$b = 85 \text{ ft}$$

$$Z = 3:1$$

$$S = 2.85\%$$

$$n = 0.04$$

$$Q = 2211 \text{ CFS (PMF - PRINCIPAL SPILLWAY DISCHARGE)}$$

FIND D, A, V

$$Q = \frac{K'}{n} b^{8/3} S^{1/2} \quad (\text{KING'S HANDBOOK Table 7-1})$$

$$K' = \frac{Qn}{b^{8/3} S^{1/2}} = \frac{(2211)(0.04)}{(85)^{2.67} (0.0285)^{1/2}} = 0.003115$$

INTERPOLATE

$$\frac{.03 - .02}{.00413 - .00223} = \frac{x}{.00575 - .00223}$$

$$\frac{D}{b} = 0.0069 + 0.02 = 0.0269$$

$$D = 0.0269 (85) = 2.29'$$

$$A = (85 \times 2.29) + (6.9 \times 2.29) = 210.4 \text{ ft}^2$$

$$V = \frac{Q}{A} = \frac{2211}{210.4} = 10.5 \text{ ft/sec}$$



Check for CRITICAL DEPTH

$$K_c' = \frac{Q}{b^{5/2}} \quad (\text{KINGS HANDBOOK TABLE B-5})$$

$$= \frac{2211}{85^{5/2}} = 0.0332$$

$$\frac{D_{c1} - 0.03}{0.0483 - 0.0352} = \frac{x}{0.0332 - 0.0252} \quad x = 0.0013$$

$$\frac{D_c}{b} = 0.0013 + 0.03 = 0.0313$$

$$D_c = 0.0313 (35) = 2.66'$$

$D_c = 2.66'$ \neq $D_u = 2.29'$ \therefore supercritical flow exists @ the end of the emergency spillway

VELOCITY @ SPILLWAY CREST (@ DAM SECTION)

$$\frac{V^2}{2g} = \frac{D}{2} \quad (\text{ASCE HANDBOOK})$$

$$V = \sqrt{2gD}$$

$$= \sqrt{2(32.2)(2.29)} = 38.5 \text{ ft/sec}$$

HEC-1 FLOOD HYDROGRAPH COMPUTATIONS

RTIOS= 0.10 0.20 0.30 0.40 0.50 0.60 0.70 0.80 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH, SNYDER METHOD
ISTAG IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO

IHYDG IUHQ TAREA SNAP TRSDA TRSPC RATIO ISNDW ISAME CAL

SPFE PMS R6 R12 R24 R48 R72 R96
0.00 19.70 111.00 122.00 133.00 143.00

LRDPT STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSHX RTIMP

UNIT HYDROGRAPH DATA
TP= 2.25 CP=0.63 NTA= 0

RECESSION DATA
STRIG= -2.00 GRCSN= -0.10 RTIOR= 1.30
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.21 AND R= 4.14 INTERVALS

UNIT HYDROGRAPH 25 END-OF-PERIOD ORIGINATES, LAG= 2.25 HOURS, CP= 0.63 VOL= 1.00

MO	DA	HR	MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW	CMPT	COMP
1	01	0	30	1	0.01	0.00	0.01	1.02	61	0.18
1	01	1	00	2	0.01	0.00	0.01	1.02	62	0.13
1	01	1	30	3	0.01	0.00	0.01	1.02	63	0.13
1	01	2	00	4	0.01	0.00	0.01	1.02	64	0.18
1	01	2	30	5	0.01	0.00	0.01	1.02	65	0.18
1	01	3	00	6	0.01	0.00	0.01	1.02	66	0.18
1	01	3	30	7	0.01	0.00	0.01	1.02	67	0.18
1	01	4	00	8	0.01	0.00	0.01	1.02	68	0.18
1	01	4	30	9	0.01	0.00	0.01	1.02	69	0.18
1	01	5	00	10	0.01	0.00	0.01	1.02	70	0.18
1	01	5	30	11	0.01	0.00	0.01	1.02	71	0.18
1	01	6	00	12	0.01	0.00	0.01	1.02	72	0.18
1	01	6	30	13	0.01	0.00	0.01	1.02	73	1.04
1	01	7	00	14	0.01	0.00	0.01	1.02	74	1.04
1	01	7	30	15	0.01	0.00	0.01	1.02	75	1.31
1	01	8	00	16	0.01	0.00	0.01	1.02	76	1.31
1	01	8	30	17	0.01	0.00	0.01	1.02	77	1.64
1	01	9	00	18	0.01	0.00	0.01	1.02	78	1.64
1	01	9	30	19	0.01	0.00	0.01	1.02	79	1.94

[illegible]

PAGE 0004

C-15

9	0115	1
10	0016	1
10	3017	1
11	0018	1
11	3019	1
12	0020	1

#FJ, \Gamma 12 1

	HYDROGRAPH AT STA	1 FOR PLAN 1, RTIO 1	72-HOUR	TOTAL	VOLUME
0	0	0	0	0	0
0	0	0	0	0	0
0	0	0	0	0	0
1	0	0	0	0	0
2	0	0	0	0	0
3	0	0	0	0	0
4	0	0	0	0	0
5	0	0	0	0	0
6	0	0	0	0	0
7	0	0	0	0	0
8	0	0	0	0	0
9	0	0	0	0	0
10	0	0	0	0	0
11	0	0	0	0	0
12	0	0	0	0	0
13	0	0	0	0	0
14	0	0	0	0	0
15	0	0	0	0	0
16	0	0	0	0	0
17	0	0	0	0	0
18	0	0	0	0	0
19	0	0	0	0	0
20	0	0	0	0	0
21	0	0	0	0	0
22	0	0	0	0	0
23	0	0	0	0	0
24	0	0	0	0	0
25	0	0	0	0	0
26	0	0	0	0	0
27	0	0	0	0	0
28	0	0	0	0	0
29	0	0	0	0	0
30	0	0	0	0	0
31	0	0	0	0	0
32	0	0	0	0	0
33	0	0	0	0	0
34	0	0	0	0	0
35	0	0	0	0	0
36	0	0	0	0	0
37	0	0	0	0	0
38	0	0	0	0	0
39	0	0	0	0	0
40	0	0	0	0	0
41	0	0	0	0	0
42	0	0	0	0	0
43	0	0	0	0	0
44	0	0	0	0	0
45	0	0	0	0	0
46	0	0	0	0	0
47	0	0	0	0	0
48	0	0	0	0	0
49	0	0	0	0	0
50	0	0	0	0	0
51	0	0	0	0	0
52	0	0	0	0	0
53	0	0	0	0	0
54	0	0	0	0	0
55	0	0	0	0	0
56	0	0	0	0	0
57	0	0	0	0	0
58	0	0	0	0	0
59	0	0	0	0	0
60	0	0	0	0	0
61	0	0	0	0	0
62	0	0	0	0	0
63	0	0	0	0	0
64	0	0	0	0	0
65	0	0	0	0	0
66	0	0	0	0	0
67	0	0	0	0	0
68	0	0	0	0	0
69	0	0	0	0	0
70	0	0	0	0	0
71	0	0	0	0	0
72	0	0	0	0	0
73	0	0	0	0	0
74	0	0	0	0	0
75	0	0	0	0	0
76	0	0	0	0	0
77	0	0	0	0	0
78	0	0	0	0	0
79	0	0	0	0	0
80	0	0	0	0	0
81	0	0	0	0	0
82	0	0	0	0	0
83	0	0	0	0	0
84	0	0	0	0	0
85	0	0	0	0	0
86	0	0	0	0	0
87	0	0	0	0	0
88	0	0	0	0	0
89	0	0	0	0	0
90	0	0	0	0	0
91	0	0	0	0	0
92	0	0	0	0	0
93	0	0	0	0	0
94	0	0	0	0	0
95	0	0	0	0	0
96	0	0	0	0	0
97	0	0	0	0	0
98	0	0	0	0	0
99	0	0	0	0	0
100	0	0	0	0	0

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
594	421	154	66	787
17	12	4	2	223
	3 41	5 00	5 31	5 31
	86 53	126 90	134 86	134 86
	209	306	325	325
	258	378	401	401

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 3

[illegible]

THOUS CU M	AC-FT	INCHES	CMS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
1485	1053	386	164	19692					
42	30	11	5	358					
	8.52	12.49	13.27	13.27					
	216.33	317.26	337.15	337.15					
	522	766	814	814					
	644	944	1004	1004					

THOUS CU M	AC-FT	INCHES	CMS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
103	106	106	106	106	106	106	106	106	106
1210	1486	1486	1486	1486	1486	1486	1486	1486	1486
577	464	464	464	464	464	464	464	464	464
151	145	145	145	145	145	145	145	145	145
100	96	96	96	96	96	96	96	96	96

THOUS CU M	AC-FT	INCHES	CMS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
1782	1264	463	197	23630					
50	36	13	6	669					
	10.22	14.99	15.93	15.93					
	259.60	380.71	404.59	404.59					
	627	919	976	976					
	773	1133	1204	1204					

THOUS CU M	AC-FT	INCHES	CMS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
2079	1474	540	230	27588					
59	42	15	8	781					
	11.52	17.49	18.58	18.58					
	302.87	444.16	472.02	472.02					
	731	1072	1139	1139					
	902	1322	1405	1405					

THOUS CU M	AC-FT	INCHES	CMS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
2079	1474	540	230	27588					
59	42	15	8	781					
	11.52	17.49	18.58	18.58					
	302.87	444.16	472.02	472.02					
	731	1072	1139	1139					
	902	1322	1405	1405					

[illegible][illegible]

*****	*****	*****	*****	*****
HYDROGRAPH ROUTING				
RESERVOIR ROUTING	MODIFIED PULS METHOD	JPLT	JPR1	INAME
IStaG	lCOMP	IECON	ITAPE	ISTAGE
1	1	0	0	1
GLOSS	Avg	ROUTING DATA		
0 0	0 00	IRCS	ISAME	LSTR
		1	1	0
NSTPS	NSTDt	LAG	AMSKK	ISPRAT
		X	TSK	STORA
IAUTO 0				

C-21

PEAK OUTFLOW IS 97 AT TIME 45 50 HOURS

1 JAN 1964


STATION 11

INFLOW(I),	OUTFLOW(O)	AND OBSERVED FLOW(*)
80.	120	200.
	160	240.

[illegible]

FLAHERTY GIAVARA ASSOCIATES, P.C.

18.30	370	I
19.00	380	I
19.30	390	01
20.00	400	01
20.30	410	I
21.00	420	I
21.30	430	I
22.00	440	I
22.30	450	I
23.00	460	I
23.30	470	I
24.00	480	I
24.30	490	I
25.00	500	I
25.30	510	I
26.00	520	I
26.30	530	I
27.00	540	I
27.30	550	I
28.00	560	I
28.30	570	I
29.00	580	I
29.30	590	I
30.00	600	I
30.30	610	I
31.00	620	I
31.30	630	I
32.00	640	I
32.30	650	I
33.00	660	I
33.30	670	I
34.00	680	I
34.30	690	I
35.00	700	I
35.30	710	I
36.00	720	I
36.30	730	I
37.00	740	I
37.30	750	I
38.00	760	I
38.30	770	I
39.00	780	I
39.30	790	I
40.00	800	I
40.30	810	I
41.00	820	I
41.30	830	I
42.00	840	I
42.30	850	I
43.00	860	I
43.30	870	I
44.00	880	I
44.30	890	I
45.00	900	I
45.30	910	I
46.00	920	I
46.30	930	I
47.00	940	I



1 * () * 1

STATION	1.	PLAN 1.	RATIO 2
END-OF-PERIOD HYDROGRAPH ORDINATES			
OUTFLOW	0	0	0
0	0	0	0
1	0	0	0
2	0	0	0
3	0	0	0
4	0	0	0
5	0	0	0
6	0	0	0
7	0	0	0
8	0	0	0
9	0	0	0
10	0	0	0
11	0	0	0
12	0	0	0
13	0	0	0
14	0	0	0
15	0	0	0
16	0	0	0
17	0	0	0
18	0	0	0
19	0	0	0
20	0	0	0
21	0	0	0
22	0	0	0
23	0	0	0
24	0	0	0
25	0	0	0
26	0	0	0
27	0	0	0
28	0	0	0
29	0	0	0
30	0	0	0
31	0	0	0
32	0	0	0
33	0	0	0
34	0	0	0
35	0	0	0
36	0	0	0
37	0	0	0
38	0	0	0
39	0	0	0
40	0	0	0
41	0	0	0
42	0	0	0
43	0	0	0
44	0	0	0
45	0	0	0
46	0	0	0
47	0	0	0
48	0	0	0
49	0	0	0
50	0	0	0
51	0	0	0
52	0	0	0
53	0	0	0
54	0	0	0
55	0	0	0
56	0	0	0
57	0	0	0
58	0	0	0
59	0	0	0
60	0	0	0
61	0	0	0
62	0	0	0
63	0	0	0
64	0	0	0
65	0	0	0
66	0	0	0
67	0	0	0
68	0	0	0
69	0	0	0
70	0	0	0
71	0	0	0
72	0	0	0
73	0	0	0
74	0	0	0
75	0	0	0
76	0	0	0
77	0	0	0
78	0	0	0
79	0	0	0
80	0	0	0
81	0	0	0
82	0	0	0
83	0	0	0
84	0	0	0
85	0	0	0
86	0	0	0
87	0	0	0
88	0	0	0
89	0	0	0
90	0	0	0
91	0	0	0
92	0	0	0
93	0	0	0
94	0	0	0
95	0	0	0
96	0	0	0
97	0	0	0
98	0	0	0
99	0	0	0
100	0	0	0

61	77	95	115	134	152	168	180	190	196
201	204	205	205	205	203	201	199	197	195
193	190	188	185	183	180	177	174	171	168
165	162	159	156	153	150	146	143	140	136
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1
102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1	102 1
102 2	102 2	102 3	102 3	102 3	102 4	102 5	102 5	102 6	102 7
103 2	103 2	103 3	103 3	103 3	103 4	103 5	103 5	103 6	103 7
103 8	103 9	103 9	103 9	103 9	103 9	103 8	103 8	103 8	103 7
103 7	103 6	103 6	103 5	103 5	103 5	103 4	103 4	103 3	103 3
103 2	103 1	103 1	103 0	103 0	104 9	104 9	104 8	104 7	104 7

PEAK OUTFLOW IS 107 AT TIME 47.00 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
107	107	91	38	4283
3	3	3	1	130
CFS	0.87	2.95	3.09	3.09
CMS	22.07	74.85	78.47	78.47
INCHES	53	181	189	189
MM	66	223	234	234
AC-FT				
THOUS CU M				

1*OVF*

STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

	200	300	400	500	600
0 11					
0 30					
1 30					
2 30					
3 30					
4 30					
5 00					
5 30					
6 00					
6 30					
7 00					
7 30					
8 00					
8 30					
9 00					
9 30					
10 00					
10 30					
11 00					
11 30					
12 00					

FLAHERTY GIAVARA ASSOCIATES, P C

12 30 251
 13 00 261
 14 30 271
 15 00 281
 16 30 291
 17 00 301
 18 00 311
 19 00 321
 20 00 3301
 21 00 3401
 22 00 350
 23 00 360
 24 00 370
 25 00 380
 26 00 390
 27 00 4001
 28 00 411
 29 00 421
 30 00 431
 31 00 441
 32 00 4510
 33 00 4610
 34 00 4710
 35 00 4810
 36 00 4910
 37 00 501
 38 00 511
 39 00 521
 40 00 531
 41 00 541
 42 00 551
 43 00 5601
 44 00 5701
 45 00 5801
 46 00 5901
 47 00 6001
 48 00 6101
 49 00 6201
 50 00 631
 51 00 641
 52 00 6501
 53 00 6601
 54 00 6701
 55 00 6801
 56 00 6901
 57 00 7001
 58 00 7101
 59 00 7201
 60 00 7301
 61 00 7401
 62 00 7501
 63 00 7601
 64 00 7701
 65 00 7801
 66 00 7901
 67 00 8001
 68 00 8101
 69 00 8201

17	30	83	17	30	84	17	30	85	17	30	86	17	30	87	17	30	88	17	30	89	17	30	90	17	30	91	17	30	92	17	30	93	17	30	94	17	30	95	17	30	96	17	30	97	17	30	98	17	30	99	17	30	100	17	30	101	17	30	102	17	30	103	17	30	104	17	30	105	17	30	106	17	30	107	17	30	108	17	30	109	17	30	110	17	30	111	17	30	112	17	30	113	17	30	114	17	30	115	17	30	116	17	30	117	17	30	118	17	30	119	17	30	120	17	30	121	17	30	122	17	30	123	17	30	124	17	30	125	17	30	126	17	30	127	17	30	128	17	30	129	17	30	130	17	30	131	17	30	132	17	30	133	17	30	134	17	30	135	17	30	136	17	30	137	17	30	138	17	30	139	17	30	140	17	30	141	17	30	142	17	30	143	17	30	144	17	30	145	17	30	146	17	30	147	17	30	148	17	30	149	17	30	150	17	30	151	17	30	152	17	30	153	17	30	154	17	30	155	17	30	156	17	30	157	17	30	158	17	30	159	17	30	160	17	30	161	17	30	162	17	30	163	17	30	164	17	30	165	17	30	166	17	30	167	17	30	168	17	30	169	17	30	170	17	30	171	17	30	172	17	30	173	17	30	174	17	30	175	17	30	176	17	30	177	17	30	178	17	30	179	17	30	180	17	30	181	17	30	182	17	30	183	17	30	184	17	30	185	17	30	186	17	30	187	17	30	188	17	30	189	17	30	190	17	30	191	17	30	192	17	30	193	17	30	194	17	30	195	17	30	196	17	30	197	17	30	198	17	30	199	17	30	200	17	30	201	17	30	202	17	30	203	17	30	204	17	30	205	17	30	206	17	30	207	17	30	208	17	30	209	17	30	210	17	30	211	17	30	212	17	30	213	17	30	214	17	30	215	17	30	216	17	30	217	17	30	218	17	30	219	17	30	220	17	30	221	17	30	222	17	30	223	17	30	224	17	30	225	17	30	226	17	30	227	17	30	228	17	30	229	17	30	230	17	30	231	17	30	232	17	30	233	17	30	234	17	30	235	17	30	236	17	30	237	17	30	238	17	30	239	17	30	240	17	30	241	17	30	242	17	30	243	17	30	244	17	30	245	17	30	246	17	30	247	17	30	248	17	30	249	17	30	250	17	30	251	17	30	252	17	30	253	17	30	254	17	30	255	17	30	256	17	30	257	17	30	258	17	30	259	17	30	260	17	30	261	17	30	262	17	30	263	17	30	264	17	30	265	17	30	266	17	30	267	17	30	268	17	30</
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	----	-----	----	------

C-27

NO

STATION 1, PLAN 1, RATIO 3
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

[illegible]

PEAK OUTFLOW IS 108. AT TIME 48.00 HOURS

CFS
 CMS
 INCHES
 MM
 AC-FT
 THOUS CU M

PEAK	6-HOUR	24-HOUR	72-HOUR
10B	108	92	41
3	3	3	1
	0.87	3.08	3.30
	22.22	78.33	83.76
	54	189	202
	66	233	249

TOTAL VOLUME	4892
	139
	3.30
	83.76
	202
	249

1 * Q * 1


STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

0	1	1	2	3	4	5	6	7	8	9	10	11	12
30	00	30	00	30	00	30	00	30	00	30	00	30	00
0	1	2	3	4	5	6	7	8	9	10	11	12	

FLAHERTY GIAVARA ASSOCIATES, P. C.

[illegible]



1*OVH*

STATION 1, PLAN 1, RATIO 4
END-OF-PERIOD HYDROGRAPH ORDINATES

PAGE 0021

C-32

FLAHERTY GIAVARA ASSOCIATES, P. C

5 30 5901
6 30 6001
7 30 6101
8 30 6201
9 30 6301
10 30 6401
11 30 6501
12 30 6601
13 30 6701
14 30 6801
15 30 6901
16 30 7001
17 30 7101
18 30 7201
19 30 7301
20 30 7401
21 30 7501
22 30 7601
23 30 7701
24 30 7801
25 30 7901
26 30 8001
27 30 8101
28 30 8201
29 30 8301
30 30 8401
31 30 8501
32 30 8601
33 30 8701
34 30 8801
35 30 8901
36 30 9001
37 30 9101
38 30 9201
39 30 9301
40 30 9401
41 30 9501
42 30 9601
43 30 9701
44 30 9801
45 30 9901
50 30 10001
51 30 10101
52 30 10201
53 30 10301
54 30 10401
55 30 10501
56 30 10601
57 30 10701
58 30 10801
59 30 10901
60 30 11001
61 30 11101
62 30 11201
63 30 11301
64 30 11401
65 30 11501

10	30117	11000
11	00118	11
11	30119	11
12	00120	

1 * Q * 1 *

[illegible]

PEAK OUTFLOW IS 517 AT TIME 45 50 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1	1.0	1.0	1.0	3.0
2	1.0	1.0	1.0	3.0
3	1.0	1.0	1.0	3.0
4	1.0	1.0	1.0	3.0
5	1.0	1.0	1.0	3.0
6	1.0	1.0	1.0	3.0
7	1.0	1.0	1.0	3.0
8	1.0	1.0	1.0	3.0
9	1.0	1.0	1.0	3.0
10	1.0	1.0	1.0	3.0
11	1.0	1.0	1.0	3.0
12	1.0	1.0	1.0	3.0
13	1.0	1.0	1.0	3.0
14	1.0	1.0	1.0	3.0
15	1.0	1.0	1.0	3.0
16	1.0	1.0	1.0	3.0
17	1.0	1.0	1.0	3.0
18	1.0	1.0	1.0	3.0
19	1.0	1.0	1.0	3.0
20	1.0	1.0	1.0	3.0
21	1.0	1.0	1.0	3.0
22	1.0	1.0	1.0	3.0
23	1.0	1.0	1.0	3.0
24	1.0	1.0	1.0	3.0
25	1.0	1.0	1.0	3.0
26	1.0	1.0	1.0	3.0
27	1.0	1.0	1.0	3.0
28	1.0	1.0	1.0	3.0
29	1.0	1.0	1.0	3.0
30	1.0	1.0	1.0	3.0
31	1.0	1.0	1.0	3.0
32	1.0	1.0	1.0	3.0
33	1.0	1.0	1.0	3.0
34	1.0	1.0	1.0	3.0
35	1.0	1.0	1.0	3.0
36	1.0	1.0	1.0	3.0
37	1.0	1.0	1.0	3.0
38	1.0	1.0	1.0	3.0
39	1.0	1.0	1.0	3.0
40	1.0	1.0	1.0	3.0
41	1.0	1.0	1.0	3.0
42	1.0	1.0	1.0	3.0
43	1.0	1.0	1.0	3.0
44	1.0	1.0	1.0	3.0
45	1.0	1.0	1.0	3.0
46	1.0	1.0	1.0	3.0
47	1.0	1.0	1.0	3.0
48	1.0	1.0	1.0	3.0
49	1.0	1.0	1.0	3.0
50	1.0	1.0	1.0	3.0
51	1.0	1.0	1.0	3.0
52	1.0	1.0	1.0	3.0
53	1.0	1.0	1.0	3.0
54	1.0	1.0	1.0	3.0
55	1.0	1.0	1.0	3.0
56	1.0	1.0	1.0	3.0
57	1.0	1.0	1.0	3.0
58	1.0	1.0	1.0	3.0
59	1.0	1.0	1.0	3.0
60	1.0	1.0	1.0	3.0
61	1.0	1.0	1.0	3.0
62	1.0	1.0	1.0	3.0
63	1.0	1.0	1.0	3.0
64	1.0	1.0	1.0	3.0
65	1.0	1.0	1.0	3.0
66	1.0	1.0	1.0	3.0
67	1.0	1.0	1.0	3.0
68	1.0	1.0	1.0	3.0
69	1.0	1.0	1.0	3.0
70	1.0	1.0	1.0	3.0
71	1.0	1.0	1.0	3.0
72	1.0	1.0	1.0	3.0
73	1.0	1.0	1.0	3.0
74	1.0	1.0	1.0	3.0
75	1.0	1.0	1.0	3.0
76	1.0	1.0	1.0	3.0
77	1.0	1.0	1.0	3.0
78	1.0	1.0	1.0	3.0
79	1.0	1.0	1.0	3.0
80				

CFS
CMS
INCHES
MM
AC-FT
THOUS CU M

517
15

425
12
3.44
87.39
211
260

213.
6
6.89
175.09
423.
521.

90.
3
7.25
184.13
444.
548.

10754.
305
7.25
184.13
444.
548.

1*DVf*

STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

	200	400	600	800	1000	1200	1400	1600	0	0	0	0	0
0 30	0 1												
1 00	1 30	2 1											
2 30	2 30	3 1											
3 30	3 30	4 1											
4 30	4 30	5 1											
5 30	5 30	6 1											
6 30	6 30	7 1											
7 30	7 30	8 1											
8 30	8 30	9 1											
9 30	9 30	10 1											
10 30	10 30	11 1											
11 30	11 30	12 1											
12 30	12 30	13 1											
13 30	13 30	14 1											
14 30	14 30	15 1											
15 30	15 30	16 1											
16 30	16 30	17 1											
17 30	17 30	18 1											
18 30	18 30	19 1											
19 30	19 30	20 1											
20 30	20 30	21 1											
21 30	21 30	22 1											
22 30	22 30	23 1											
23 30	23 30	24 1											
24 30	24 30	25 1											
25 30	25 30	26 1											
26 30	26 30	27 1											
27 30	27 30	28 1											
28 30	28 30	29 1											
29 30	29 30	30 1											
30 30	30 30	31 1											
31 30	31 30	32 1											
32 30	32 30	33 1											
33 30	33 30	34 1											
34 30	34 30	35 1											
35 30	35 30	36 1											
36 30	36 30	37 1											
37 30	37 30	38 1											
38 30	38 30	39 1											
39 30	39 30	40 1											
40 30	40 30	41 1											
41 30	41 30	42 1											
42 30	42 30	43 1											
43 30	43 30	44 1											
44 30	44 30	45 1											
45 30	45 30	46 1											
46 30	46 30	47 1											
47 30	47 30	48 1											
48 30	48 30	49 1											
49 30	49 30	50 1											
50 30	50 30	51 1											
51 30	51 30	52 1											
52 30	52 30	53 1											
53 30	53 30	54 1											
54 30	54 30	55 1											
55 30	55 30	56 1											
56 30	56 30	57 1											
57 30	57 30	58 1											
58 30	58 30	59 1											
59 30	59 30	60 1											
60 30	60 30	61 1											
61 30	61 30	62 1											
62 30	62 30	63 1											
63 30	63 30	64 1											
64 30	64 30	65 1											
65 30	65 30	66 1											
66 30	66 30	67 1											
67 30	67 30	68 1											
68 30	68 30	69 1											
69 30	69 30	70 1											
70 30	70 30	71 1											
71 30	71 30	72 1											
72 30	72 30	73 1											
73 30	73 30	74 1											
74 30	74 30	75 1											
75 30	75 30	76 1											
76 30	76 30	77 1											
77 30	77 30	78 1											
78 30	78 30	79 1											
79 30	79 30	80 1											
80 30	80 30	81 1											
81 30	81 30	82 1											
82 30	82 30	83 1											
83 30	83 30	84 1											
84 30	84 30	85 1											
85 30	85 30	86 1											
86 30	86 30	87 1											
87 30	87 30	88 1											
88 30	88 30	89 1											
89 30	89 30	90 1											
90 30	90 30	91 1											
91 30	91 30	92 1											
92 30	92 30	93 1											
93 30	93 30	94 1											
94 30	94 30	95 1											
95 30	95 30	96 1											
96 30	96 30	97 1											
97 30	97 30	98 1											
98 30	98 30	99 1											
99 30	99 30	100 1											

FLAHERTY GIAVARA ASSOCIATES, P C

23 30 4710
 0 00 4810
 0 30 4910
 1 00 5010
 1 30 5110
 2 00 5210
 3 30 5310
 3 30 5410
 4 00 5510
 4 30 5610
 5 00 5710
 5 30 5810
 6 00 5910
 6 30 6010
 7 00 6110
 7 30 6210
 8 00 6310
 8 30 6410
 9 00 6510
 9 30 6610
 10 00 6710
 10 30 6810
 11 00 6910
 11 30 7010
 12 00 7110
 12 30 7210
 13 00 7310
 13 30 7410
 14 00 7510
 14 30 7610
 15 00 7710
 15 30 7810
 16 00 7910
 16 30 8010
 17 00 8110
 17 30 8210
 18 00 8310
 18 30 8410
 19 00 8510
 19 30 8610
 20 00 8710
 20 30 8810
 21 00 8910
 21 30 9010
 22 00 9110
 22 30 9210
 23 00 9310
 23 30 9410
 24 00 9510
 24 30 9610
 25 00 9710
 25 30 9810
 26 00 9910
 26 30 10010
 27 00 10110
 27 30 10210
 28 00 10310
 28 30 10410

[illegible]

STATION 1, PLAN 1, RATIO 6
END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]


PEAK OUTFLOW IS 793. AT TIME 45.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFB	793	632	89	121		14520
CMS	22	18	28	3		411
INCHES		9 11	9 36	9 79		79
MM		129.83	237.76	248.60		248.60
CU-FT		313	574	600		600
AC-M		386	708	740		740
THOUS						

#JVD#1

STATION 1

[illegible]



1*DVN*

C-40

STATION 1, PLAN 1, RATIO 7
END-OF-PERIOD HYDROGRAPH ORDINATES

STATION	1	PLAN 1	RATIO 7	END-OF-PERIOD HYDROGRAPH ORDINATES
OUTFLOW	0	1	1	0
1	1	1	1	1
2	1	1	1	1
3	1	1	1	1
4	1	1	1	1
5	1	1	1	1
6	1	1	1	1
7	1	1	1	1
8	1	1	1	1
9	1	1	1	1
10	1	1	1	1
11	1	1	1	1
12	1	1	1	1
13	1	1	1	1
14	1	1	1	1
15	1	1	1	1
16	1	1	1	1
17	1	1	1	1
18	1	1	1	1
19	1	1	1	1
20	1	1	1	1
21	1	1	1	1
22	1	1	1	1
23	1	1	1	1
24	1	1	1	1
25	1	1	1	1
26	1	1	1	1
27	1	1	1	1
28	1	1	1	1
29	1	1	1	1
30	1	1	1	1
31	1	1	1	1
32	1	1	1	1
33	1	1	1	1
34	1	1	1	1
35	1	1	1	1
36	1	1	1	1
37	1	1	1	1
38	1	1	1	1
39	1	1	1	1
40	1	1	1	1
41	1	1	1	1
42	1	1	1	1
43	1	1	1	1
44	1	1	1	1
45	1	1	1	1
46	1	1	1	1
47	1	1	1	1
48	1	1	1	1
49	1	1	1	1
50	1	1	1	1
51	1	1	1	1
52	1	1	1	1
53	1	1	1	1
54	1	1	1	1
55	1	1	1	1
56	1	1	1	1
57	1	1	1	1
58	1	1	1	1
59	1	1	1	1
60	1	1	1	1
61	1	1	1	1
62	1	1	1	1
63	1	1	1	1
64	1	1	1	1
65	1	1	1	1
66	1	1	1	1
67	1	1	1	1
68	1	1	1	1
69	1	1	1	1
70	1	1	1	1
71	1	1	1	1
72	1	1	1	1
73	1	1	1	1
74	1	1	1	1
75	1	1	1	1
76	1	1	1	1
77	1	1	1	1
78	1	1	1	1
79	1	1	1	1
80	1	1	1	1
81	1	1	1	1
82	1	1	1	1
83	1	1	1	1
84	1	1	1	1
85	1	1	1	1
86	1	1	1	1
87	1	1	1	1
88	1	1	1	1
89	1	1	1	1
90	1	1	1	1
91	1	1	1	1
92	1	1	1	1
93	1	1	1	1
94	1	1	1	1
95	1	1	1	1
96	1	1	1	1
97	1	1	1	1
98	1	1	1	1
99	1	1	1	1
100	1	1	1	1
101	1	1	1	1
102	1	1	1	1
103	1	1	1	1
104	1	1	1	1
105	1	1	1	1
106	1	1	1	1
107	1	1	1	1
108	1	1	1	1
109	1	1	1	1
110	1	1	1	1
111	1	1	1	1
112	1	1	1	1
113	1	1	1	1
114	1	1	1	1
115	1	1	1	1
116	1	1	1	1
117	1	1	1	1
118	1	1	1	1
119	1	1	1	1
120	1	1	1	1
121	1	1	1	1
122	1	1	1	1
123	1	1	1	1
124	1	1	1	1
125	1	1	1	1
126	1	1	1	1
127	1	1	1	1
128	1	1	1	1
129	1	1	1	1
130	1	1	1	1
131	1	1	1	1
132	1	1	1	1
133	1	1	1	1
134	1	1	1	1
135	1	1	1	1
136	1	1	1	1
137	1	1	1	1
138	1	1	1	1
139	1	1	1	1
140	1	1	1	1
141	1	1	1	1
142	1	1	1	1
143	1	1	1	1
144	1	1	1	1
145	1	1	1	1
146	1	1	1	1
147	1	1	1	1
148	1	1	1	1
149	1	1	1	1
150	1	1	1	1
151	1	1	1	1
152	1	1	1	1
153	1	1	1	1
154	1	1	1	1
155	1	1	1	1
156	1	1	1	1
157	1	1	1	1
158	1	1	1	1
159	1	1	1	1
160	1	1	1	1
161	1	1	1	1
162	1	1	1	1
163	1	1	1	1
164	1	1	1	1
165	1	1	1	1
166	1	1	1	1
167	1	1	1	1
168	1	1	1	1
169	1	1	1	1
170	1	1	1	1
171	1	1	1	1
172	1	1	1	1
173	1	1	1	1
174	1	1	1	1
175	1	1	1	1
176	1	1	1	1
177	1	1	1	1
178	1	1	1	1
179	1	1	1	1
180	1	1	1	1
181	1	1	1	1
182	1	1	1	1
183	1	1	1	1
184	1	1	1	1
185	1	1	1	1
186	1	1	1	1
187	1	1	1	1
188	1	1	1	1
189	1	1	1	1
190	1	1	1	1
191	1	1	1	1
192	1	1	1	1
193	1	1	1	1
194	1	1	1	1
195	1	1	1	1
196	1	1	1	1
197	1	1	1	1
198	1	1	1	1
199	1	1	1	1
200	1	1	1	1
201	1	1	1	1
202	1	1	1	1
203	1	1	1	1
204	1	1	1	1
205	1	1	1	1
206	1	1	1	1
207	1	1	1	1
208	1	1	1	1
209	1	1	1	1
210	1	1	1	1
211	1	1	1	1
212	1	1	1	1
213	1	1	1	1
214	1	1	1	1
215	1	1	1	1
216	1	1	1	1
217	1	1	1	1
218	1	1	1	1
219	1	1	1	1
220	1	1	1	1
221	1	1	1	1
222	1	1	1	1
223	1	1	1	1
224	1	1	1	1
225	1	1	1	1
226	1	1	1	1
227	1	1	1	1
228	1	1	1	1
229	1	1	1	1
230	1	1	1	1
231	1	1	1	1
232	1	1	1	1
233	1	1	1	1
234	1	1	1	1
235	1	1	1	1
236	1	1	1	1
237	1	1	1	1
238	1	1	1	1
239	1	1	1	1
240	1	1	1	1
241	1	1	1	1
242	1	1	1	1
243	1	1	1	1
244	1	1	1	1
245	1	1	1	1
246	1	1	1	1
247	1	1	1	1
248	1	1	1	1
249	1	1	1	1
250	1	1	1	1
251	1	1	1	1
252	1	1	1	1
253	1	1	1	1
254	1	1	1	1
255	1	1	1	1
256	1	1	1	1
257	1	1	1	1
258	1	1	1	1
259	1	1	1	1
260	1	1	1	1
261	1	1	1	1
262	1	1	1	1
263	1	1	1	1
264	1	1	1	1
265	1	1	1	1
266	1	1	1	1
267	1	1	1	1
268	1	1	1	1
269	1	1	1	1
270	1	1	1	1
271	1	1	1	1
272	1	1	1	1
273	1	1	1	1
274	1	1	1	1
275	1	1	1	1
276	1	1	1	1
277	1	1	1	1
278	1	1	1	1
279	1	1	1	1
280	1	1	1	1
281	1	1	1	1
282	1	1	1	1
283	1	1	1	1
284	1	1	1	1
285	1	1	1	1
286	1	1	1	1
287	1	1	1	1
288	1	1	1	1
289	1	1	1	1
290	1	1	1	1
291	1	1	1	1
292	1	1	1	1
293	1	1	1	1
294	1	1	1	1
295	1	1	1	

16.	17.	19.	20.	22.	25.	28.	31.	35.
38.	41.	50.	57.	68.	85.	107.	136.	173.
220.	281.	429.	497.	549.	582.	597.	598.	591.
379.	366.	338.	523.	509.	496.	483.	476.	467.
406.	452.	439.	433.	428.	418.	418.	414.	410.
	403.	397.	394.	391.	389.	386.	384.	382.
			STAGE					
102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0
102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0
102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0	102.0
102.4	102.4	102.4	102.4	102.4	102.4	102.4	102.4	102.4
102.3	102.3	102.3	102.3	102.3	102.3	102.3	102.3	102.3
102.3	102.3	102.4	102.4	102.4	102.4	102.4	102.4	102.4
102.8	102.9	102.9	102.9	103.4	103.7	104.1	104.7	105.3
106.1	107.1	108.3	110.4	111.1	111.5	111.7	111.7	111.6
109.5	111.3	110.9	110.7	110.5	110.3	110.2	110.1	109.9
109.8	109.7	109.5	109.5	109.4	109.3	109.2	109.2	109.1
109.1	109.0	108.9	108.9	108.8	108.8	108.8	108.7	108.7

PEAK OUTFLOW IS 1149 AT TIME 44.50 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1149.	892.	366.	153.	18322.
33.	24.	10.	4.	519.
CFS	CMS	INCHES	MM	THOUS CU M
175.02	6.89	11.85	12.35	12.35
423.	301.07	313.70	313.70	313.70
AC-FT	727.	737.	737.	737.
	896.	934.	934.	934.

1*OVF*

C-41


STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

	400.	800.	1200.	1600.	2000.	2400.	
0. 11							0.
1. 30							0.
2. 30							0.
3. 30							0.
4. 30							0.
5. 30							0.
6. 30							0.
7. 30							0.
8. 30							0.
9. 30							0.
10. 30							0.
11. 00							0.

11	30	231	
12	00	241	
13	00	251	
14	00	261	
15	00	271	
16	00	281	
17	00	291	
18	00	301	
19	00	311	
20	00	321	
21	00	3301	
22	00	3401	
23	00	350	
24	00	360	
25	00	370	
26	00	380	
27	00	390	
28	00	4001	
29	00	4101	
30	00	4201	
31	00	4301	
32	00	441	
33	00	451	
34	00	461	
35	00	471	
36	00	481	
37	00	491	
38	00	501	
39	00	511	
40	00	521	
41	00	531	
42	00	541	
43	00	551	
44	00	561	
45	00	571	
46	00	581	
47	00	5901	
48	00	6001	
49	00	6101	
50	00	6201	
51	00	6301	
52	00	6401	
53	00	6501	
54	00	6601	
55	00	6701	
56	00	6801	
57	00	6901	
58	00	7001	
59	00	7101	
60	00	7201	
61	00	7301	
62	00	7401	
63	00	7501	
64	00	7601	
65	00	7701	
66	00	7801	
67	00	7901	
68	00	8001	

16 30 81
17 30 82
18 30 83
19 30 84
20 30 85
21 30 86
22 30 87
23 30 88
24 30 89
25 30 90
26 30 91
27 30 92
28 30 93
29 30 94
30 30 95
31 30 96
32 30 97
33 30 98
34 30 99
35 30 100
36 30 101
37 30 102
38 30 103
39 30 104
40 30 105
41 30 106
42 30 107
43 30 108
44 30 109
45 30 110
46 30 111
47 30 112
48 30 113
49 30 114
50 30 115
51 30 116
52 30 117
53 30 118
54 30 119
55 30 120



STATION 1, PLAN 1, RATIO 8
END-OF-PERIOD HYDROGRAPH ORDINATES

STATION	OUTFLOW	END-OF-PERIOD HYDROGRAPH ORDINATES
0	0	0
1	1	1
2	1	1
3	1	1
4	1	1
5	1	1
6	1	1
7	1	1
8	1	1
9	1	1
10	1	1
11	1	1
12	1	1
13	1	1
14	1	1
15	1	1
16	1	1
17	1	1
18	1	1
19	1	1
20	1	1
21	1	1
22	1	1
23	1	1
24	1	1
25	1	1
26	1	1
27	1	1
28	1	1
29	1	1
30	1	1
31	1	1
32	1	1
33	1	1
34	1	1
35	1	1
36	1	1
37	1	1
38	1	1
39	1	1
40	1	1
41	1	1
42	1	1
43	1	1
44	1	1
45	1	1
46	1	1
47	1	1
48	1	1
49	1	1
50	1	1
51	1	1
52	1	1
53	1	1
54	1	1
55	1	1
56	1	1
57	1	1
58	1	1
59	1	1
60	1	1
61	1	1
62	1	1
63	1	1
64	1	1
65	1	1
66	1	1
67	1	1
68	1	1
69	1	1
70	1	1
71	1	1
72	1	1
73	1	1
74	1	1
75	1	1
76	1	1
77	1	1
78	1	1
79	1	1
80	1	1
81	1	1
82	1	1
83	1	1
84	1	1
85	1	1
86	1	1
87	1	1
88	1	1
89	1	1
90	1	1
91	1	1
92	1	1
93	1	1
94	1	1
95	1	1
96	1	1
97	1	1
98	1	1
99	1	1
100	1	1
101	1	1
102	1	1
103	1	1
104	1	1
105	1	1
106	1	1
107	1	1
108	1	1
109	1	1
110	1	1
111	1	1
112	1	1
113	1	1
114	1	1
115	1	1
116	1	1
117	1	1
118	1	1
119	1	1
120	1	1

108	108	200	460	807	1212	1427	1503	1446	1329
1191	1042	896	783	707	633	563	501	448	409
386	365	345	326	309	293	278	263	250	238
226	215	205	195	186	177	169	161	154	147
0	0	0	0	0	0	0	0	0	1
1	1	1	1	1	1	1	1	1	1
1	1	1	1	1	1	1	1	1	1
20	21	21	21	21	21	21	14	17	19
19	18	18	18	18	18	18	20	20	19
19	19	20	21	23	26	29	18	18	19
43	47	51	57	65	78	97	32	36	39
254	324	405	487	598	605	630	123	156	199
603	586	569	553	537	522	508	496	485	476
448	461	454	448	442	436	431	426	422	418
414	410	407	404	400	398	395	392	390	388
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0	102 0
102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4
102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4
102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4	102 4
102 9	103 0	103 1	103 2	103 3	103 5	103 6	104 4	104 7	104 8
106 7	107 8	109 0	110 2	111 3	111 6	112 1	112 3	112 7	112 8
111 8	111 6	111 3	111 1	110 9	109 7	109 5	110 3	110 2	110 1
110 0	109 8	109 8	109 7	109 6	109 5	109 4	109 4	109 3	109 2
109 2	109 1	109 1	109 0	109 0	108 9	108 9	108 9	108 8	108 8

PEAK OUTFLOW IS 1303 AT TIME 44.00 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1503	1074	443	184	22128
43	50	13	5	627
CFS	8.59	14.35	14.92	14.92
CHS	220.70	364.45	378.87	378.87
INCHES	533	880	914	914
MM	657	1085	1128	1128
AC-FT				
THOUS CU M				

1=0.1F*

STATION 1

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

400	800	1200	1500	2000	2400
0	0	0	0	0	0

0	30	11
1	00	21
1	30	31
2	00	41
2	30	51
3	00	61
3	30	71
4	00	81
4	30	91
5	00	101

AD-A107 412

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT
NATIONAL DAM SAFETY PROGRAM, LARCHWOOD LAKE DAM (INVENTORY NUMB--ETC(U)
AUG 81 H C FLAHERTY

F/G 13/13


DACW51-81-C-0006


NL

UNCLASSIFIED

2 of 3

Aug 1982






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

C-45

FLAHERTY GIAVARA ASSOCIATES, P. C.



STATION 1, PLAN 1, RATIO 9

1*OVN*

END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

PEAK OUTFLOW IS 2173. AT TIME 43.50 HOURS

	CFS	PEAK
	CMS	2173
	INCHES	62.
	MM	
	AC-FT	
	THOUS CU M	

1 #QVF *

STATION 1

C-47

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)

	400.	800.	1200.	1600.	2000.	2400.	2800.	3200.	0.	0.	0.	0.	0.
0.	11	11											
1.	21	21											
2.	31	31											
3.	41	41											
4.	51	51											
5.	61	61											
6.	71	71											
7.	81	81											
8.	91	91											
9.	101	101											
10.	111	111											
11.	121	121											
12.	131	131											
13.	141	141											
14.	151	151											
15.	161	161											
16.	171	171											
17.	181	181											
18.	191	191											
19.	201	201											
20.	211	211											
21.	221	221											
22.	231	231											
23.	241	241											
24.	251	251											
25.	261	261											
26.	271	271											
27.	281	281											
28.	291	291											
29.	301	301											
30.	311	311											
31.	321	321											
32.	3301	3301											
33.	340	340											
34.	350	350											
35.	360	360											
36.	370	370											
37.	380	380											
38.	39	39											
39.	40	40											
40.	41	41											
41.	42	42											
42.	43	43											
43.	44	44											
44.	45	45											
45.	4610	4610											
46.	4710	4710											
47.	4810	4810											
48.	4910	4910											
49.	5010	5010											
50.	5110	5110											
51.	5210	5210											
52.	5310	5310											
53.	54	54											
54.	55	55											
55.	56	56											
56.	57	57											
57.	58	58											
58.	59	59											
59.	60	60											

30 57 I
 30 58 I
 30 59 I
 30 60 I
 30 61 I
 30 62 I
 30 63 I
 30 64 01
 30 65 01
 30 66 01
 30 67 01
 30 68 01
 30 69 01
 30 70 01
 30 71 01
 30 72 01
 30 73 01
 30 74 01
 30 75 01
 30 76 01
 30 77 01
 30 78 01
 30 79 01
 30 80 01
 30 81 01
 30 82 01
 30 83 01
 30 84 01
 30 85 01
 30 86 01
 30 87 01
 30 88 01
 30 89 01
 30 90 01
 30 91 01
 30 92 01
 30 93 01
 30 94 01
 30 95 01
 30 96 01
 30 97 01
 30 98 01
 30 99 01
 30 100 01
 30 101 01
 30 102 01
 30 103 01
 30 104 01
 30 105 01
 30 106 01
 30 107 01
 30 108 01
 30 109 01
 30 110 01
 30 111 01
 30 112 01
 30 113 01
 30 114 01

APPENDIX D

PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS

DESIGN DATA SUMMARY

U.S. DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

DESIGN REPORT SUMMARY

I. Watershed Data		
A. Structure Class	C"	
B. Drainage Area	735	Ac.
C. Time of Concentration - T_c	0.54	Hrs.
D. Hydrologic Curve Number - C_n		
1. Moisture Condition II	73	
II. Principal Spillway		
A. Conduit		
1. Inside Dia.	R/Concrete Prestressed	30"
2. Length	121	Ft.
B. Riser		
1. Inside Dimensions	2.5 x 7.5	Ft.
2. Height (Floor to Crest)	19.0	Ft.
C. Weir Length	13.0	Ft.
D. Orifice Dimensions	N/A	In.
E. Reservoir Drain Size	12"	In.
F. Type of Energy Dissipater	Plunge Pool	
III. Emergency Spillway		
A. Width	85	Ft.
B. Side Slopes	3:1	
C. Length of Level Section	50	Ft.
D. Exit Slope	0.028	Ft./Ft.
E. Max. Velocity in Exit Section @ D. H. W.	6.6	Ft./Sec.
F. Duration of Flow thru Emer. Spillway @ D. H. W.	11.8	Hrs.
G. Frequency of Use	100 yr	
IV. Earth Fill		
A. Height	27	Ft.
B. Volume	11,412	C. Y.
C. Compaction	Class A	
	95%	

FILL PLACEMENT

STATE NEW YORK PROJECT LARCHWOOD LAKE
OTSEGO CO.

HYDROLOGIC AND HYDRAULIC DESIGN CALCULATIONS

LARCHWOOD LAKE
OTSEGO CO. S&WCD
NY-936-D

HYDROLOGY AND HYDRAULICS

TABLE OF CONTENTS

	<u>Page</u>
1. Criteria	
Design Criteria	1-1
Structure Classification	1-2
2. Hydrograph Computations	
Soil Cover Complex Curve Number Computations	2-1
Time of Concentration Computations	2-2, 2-3
Base Flow and Snowmelt Determination	2-4
Principal Spillway Hydrograph & Mass Curve Computations	2-5
Emergency Spillway Hydrograph Computations	2-6
Freeboard Hydrograph Computations	2-7
3. Storage Computations	
Stage Storage Computations	3-1, 3-2
Stage vs. Storage Curve	3-3
Stage vs. Area Curve	3-4
Floodwater Retarding - Determination of Emergency Spillway Crest Elevation	3-5
4. Discharge Computations	
Flow Constants	4-1
Q/b vs. Hp Computations (Emergency Spillway)	4-2
Emergency Spillway Discharge Curve	4-3
Stage Discharge Computations	4-4
Exit Channel Slope & Velocity (Emergency Spillway)	4-5
5. Time Computations	
Duration of flow through Emergency Spillway	5-1
Drawdown Time - Flood Pool	5-2
6. Flood Routing	
Principal Spillway Mass Curve	6-1
Emergency Spillway Hydrograph	6-2
Freeboard Hydrograph	6-3

LARCHWOOD LAKE

OTSEGO CO. S&WCD

NY-936-D

DESIGN CRITERIA

1. Structure Classification: Class "C".
2. Purpose; Single purpose flood retarding structure.
3. Riser:

Single stage with the riser crest set at normal water line by landowner.
4. Principal Spillway: Use 30" RCP
5. Crest of Emergency Spillway: The minimum crest elevation of the emergency spillway is set by routing through the principal spillway the PSH and PSMC developed by Chapter 21, Section 4, Hydrology, Part I. Use 100 year frequency rainfall.
6. Emergency spillway and freeboard hydrographs: Use minimum rainfall values from ES-1020 for Class "C" structures.
7. Emergency spillway:
 - a. Length of level section = 50.0 ft.
 - b. Inlet channel: $S = 0.020$
8. Earth Fill:
 - a. Top Width: Determine by $W = \frac{H+35}{5}$
 - b. Side slopes: Upstream 3:1; Downstream $2\frac{1}{2}$:1
 - c. Berm (upstream): 10' width set approx. 0.5' below crest of riser
9. Dike (along the emergency spillway):
 - a. Top Width - 12.0'
 - b. Side Slopes - 3:1

STATE NEW YORK		PROJECT LARCHWOOD LAKE - OTSEGO S. & W.C.D.			
BY J.R.M.	DATE 5/66	CHECKED BY RKC JH	DATE 5/66 7/66	JOB NO.	
SUBJECT STRUCTURE CLASSIFICATION				SHEET OF 1-2	

$$1. \frac{\text{Height} \times \text{Storage}}{1000} = \frac{26 \times 920.34}{1000} = \frac{23928.84}{1000} = 23.9$$

$\therefore K_s = 12.5$

2. Damage to Restaurant
1.25 mi. below structure and 2 houses
on County Road 1.75 mi below structure 20 People $\therefore K_p = 2.5$ ✓

3. Flood Plain Width - 350-400' $\therefore K_w = 4.5$ ✓

4. Distance to Damage Center
1) 1.25 mi
2) 1.75 mi $\therefore K_d = 0.7$ ✓

$$5. \frac{K_s + K_p + K_w}{K_d} = \frac{12.5 + 2.5 + 4.5}{0.7} = \frac{19.5}{0.7} = 27.8$$

This Structure Classification has been determined to be a Class "C" ✓

Watershed OTEGO Site LARCHWOOD LAKE 735 Acres
 Computed by JRM Date 5/66 Checked by RKC Date 5/66
A.F.H. 7/66

Cover	Practice	Condi- tion or Rela.	Acres Per Practice	Curve Numbers Moisture Cond. II			Product
				B Soils	C Soils	D Soils	
Fallow	Straight Row	--		86	91	94	
Row Crops	Straight Row	Poor		81	88	91	
	Straight Row	Good		78	85	89	
	*Contoured	Poor		79	84	88	
	*Contoured	Good		75	82	86	
	*C and T	Poor		74	80	82	
	*C and T	Good		71	78	81	
Small Grain	Straight Row	Poor		76	84	98	
	Straight Row	Good		75	83	87	
	*Contoured	Poor		74	82	85	
	*Contoured	Good		73	81	84	
	*C and T	Poor		72	79	82	
	*C and T	Good		70	78	81	
Legumes or Rotation Meadow	Straight Row	Poor		77	85	89	
	Straight Row	Good		72	81	85	
	*Contoured	Poor		75	83	85	
	*Contoured	Good		69	78	83	
	*C and T	Poor		73	80	83	
	*C and T	Good		67	76	80	
Pasture		Poor		79	86	89	
		Fair		69	79	84	
		Good	<u>142 C</u> <u>62 D</u>	61	<u>(79)</u>	<u>(80)</u>	<u>16028</u> ✓
Meadow (Permanent)		Good	<u>49</u>	58	<u>(71)</u>	78	<u>3479</u> ✓
Woods (Farm)		Poor	<u>11</u>	66	<u>(77)</u>	83	<u>847</u> ✓
		Fair		60	73	79	
		Good	<u>42 D</u> <u>422 C</u>	55	<u>(70)</u>	<u>(77)</u>	<u>32774</u> ✓
Farmsteads		--		74	82	86	
Roads	Dirt	--		82	87	89	
	(Inc. R.O.W) Hard Surface	--		84	90	92	
Impervious Surfaces		--		100	100	100	
Water Surfaces (lakes, ponds)		--		100	100	100	

Total Acres 735 Product total = 53128 ✓

Weighted Runoff Curve No. $\frac{\text{Product Total}}{\text{Total Acres}} = \frac{53128}{735} = 72.3$ ✓
USE RCN 73


- * Contoured and graded terraces
- ** Includes level terraced areas (runoff corrected by volume).

NY-155
(8-12-64)

STATE NEW YORK		PROJECT Larchwood Lake - Otsego S. & W. C. D.	
BY F. Fields	DATE 4/66	CHECKED BY JRM / LK	DATE 5/66 7/66
SUBJECT Estimate of "n" Value For Inlet Channel			JOB NO.
			SHEET OF 2-2

- ① Channel in Earth Basic "n" = 0.020
- ② Surface Irregularity (Moderate) Modifying Value = 0.010
- ③ Variations In Shape (^{to small all} Gradual) Modifying Value = 0.005
- ④ Obstructions MINOR Modifying Value = 0.010
- ⑤ Vegetation Low $\frac{0.005}{n_s = 0.050}$
- ⑥ $\frac{p_m}{p_s}$ Minor $\frac{0.000}{n = 0.05}$

FROM Aerial Photo No. EHH-4AA-78
Scale 1" = 1667'



STATE	NEW YORK	PROJECT	LARCHWOOD LAKE - OTSEGO S.F.W.C.D.
BY	F. Fields	CHECKED BY	JRM
DATE	4/66	DATE	5/66
SUBJECT	TIME OF CONCENTRATION COMPS.		SHEET 2-3

Reach *I 650 L.F. Defined Channel

$$V = \frac{1.486 r^{2/3} S^{1/2}}{n} = \frac{1.486 (1.0)^{2/3} (.03)^{1/2}}{0.05} = 5.15 \text{ F/S } \frac{650}{5.15} = 126 \text{ SEC.}$$

Reach *II 500 L.F. Defined Channel

$$V = \frac{1.486 r^{2/3} S^{1/2}}{n} = \frac{1.486 (1.15)^{2/3} (.03)^{1/2}}{0.05} = 6.00 \text{ F/S } \frac{500}{6.00} = 83 \text{ SEC}$$

Reach *III 2100 L.F. Channel & Draw

$$V = \frac{1.486 r^{2/3} S^{1/2}}{n} = \frac{1.486 (.62)^{2/3} (.035)^{1/2}}{0.05} = 4.04 \text{ F/S } \frac{2100}{4.04} = 520 \text{ SEC.}$$

Reach *IV 1835 L.F. Overland Flow

Pasture 4-7 % Slope = 1.5 F/S

$$\frac{1835}{1.5} = 1223 \text{ SEC.}$$

Total 1952 SEC

$$T.C. = \frac{1952 \text{ SEC}}{3600 \text{ SEC/HRS.}} = 0.54 \text{ HRS.}$$

STATE	NEW YORK	PROJECT	LARCHWOOD LAKE - OTSEGO S.F.W.C.D.
BY	RKC	DATE	5/66
CHECKED BY	TRM	DATE	5/66
SUBJECT	PRINCIPLE SPILLWAY	JOB NO.	
		SHEET	OF 2-4

100-YEAR FREQUENCY

1 DAY RAINFALL				10 DAY RAINFALL			Q_1 / Q_{10}	T.C. (HRS)	D.A. (SQ MI)	SERIAL NO
SITE	RCN AMC II	RAINFALL (IN.)	RUNOFF Q.	R.C.N. AMC II	RAINFALL (IN.)	RUNOFF Q ₁₀				
1	73	5.70	2.84	56	10.00	4.36	0.651	0.54	1.15	6

SNOW MELT OR BASE FLOW

USE VALUE FROM N.Y. STATE MAP - MINIMUM RUNOFF (INCHES/DAY)
FOR DEVELOPING THE PSH & PSMC 2/66

USE 0.6"/DAY

CPD 1888 G-470067

STATE	NEW YORK	PROJECT	LARCHWOOD LAKE - OTSEGO S.F.W.C.D.		
BY	RKC	DATE	5/66	CHECKED BY	JRM
SUBJECT	P.S.H. & P.S.M.C.		DATE	5/66	JOB NO.
					SHEET OF 2-5

$$Q_{10} = 4.36 \quad A = 1.15 \text{ Sq Mi.}$$

$$AQ_{10} = 5.01 \text{ mi}^2\text{-inches}$$

TIME	Preliminary P.S.H	SNOW MELT	P.S.H	Preliminary P.S.M.C.	Acc. Snow MELT	P.S.	M.C.
DAYS	C.F.S.	C.F.S.	C.F.S.	Inches	Inches	Inches	Ac. Ft.
0.0	0	19	19	0.000	0.00	0.00	0
0.1	2		21	0.003	0.06	0.06	4
0.5	2		21	0.030	0.30	0.33	20
1.0	3		22	0.072	0.60	0.67	41
2.0	3		22	0.163	1.20	1.36	83
3.0	4		23	0.285	1.80	2.09	128
3.5	6		25	0.368	2.10	2.47	151
4.0	7		26	0.477	2.40	2.88	176
4.2	10		29	0.533	2.52	3.05	187
4.4	14		33	0.610	2.64	3.25	199
4.6	17		36	0.707	2.76	3.47	213
4.7	21		40	0.766	2.82	3.59	220
4.8	28		47	0.842	2.88	3.72	228
4.9	45		64	0.957	2.94	3.90	239
5.0	550		569	1.885	3.00	4.89	300
5.1	184		203	3.028	3.06	6.09	373
5.2	65		84	3.416	3.12	6.54	401
5.3	32		51	3.568	3.18	6.75	413
5.4	21		40	3.650	3.24	6.89	422
5.5	17		36	3.709	3.30	7.01	429
5.6	13		32	3.756	3.36	7.12	436
5.8	10		29	3.824	3.48	7.30	447
6.0	8		27	3.879	3.60	7.48	458
6.5	7		26	3.990	3.90	7.89	483
7.0	5		24	4.074	4.20	8.27	507
8.0	4		23	4.197	4.80	9.00	551
9.0	3		22	4.290	5.40	9.69	594
10.0	2		21	4.355	6.00	10.36	635
10.1	0		19	4.360	6.06	10.42	638
10.3	0		19	4.360	6.18	10.54	646

1/	735 ARCES	=	61.25	AC. FT.
	12 IN/FT			IN

HYDROGRAPH COMPUTATION

SHT. 2-6

WATERSHED OR PROJECT LARCHWOOD LAKE STATE NEW YORKSTRUCTURE SITE OR SUBAREA OTSEGO CO.DR. AREA 115 SQ. MI.T_r .54 HR.RUNOFF CONDITION NO. IIRUNOFF CURVE NO. 73 STORM DISTRIB. CURVE B HYDROGRAPH FAMILY NO. 2STORM DURATION 6 HR.RAINFALL 9.1 X 1.33 POINT 12.1 IN.AREAL 12.1 IN.Q 8.57 IN.COMPUTED T_p .54(1.7) HR. 0.38T_r 5.18 HR.(T_r + T_p) 5.18 / 0.38 COMPUTED 13.63USED 16REVISED T_p 0.324 $q_p = \frac{484 A}{REV. T_p} = \frac{1718}{0.324}$ CFS.Q_q = 14,723 CFS.(COLUMN) = (1/T_p) REV. T_p.(COLUMN) = (q_p/Q_q) Q_q.

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	0	0	21	5.83	88	41		
2	0.29	29	22	6.12	44	42		
3	0.58	103	23	6.42	15	43		
4	0.87	294	24	6.71	0	44		
5	1.17	545	25			45		
6	1.46	2179	26			46		
7	1.75	4078	27			47		
8	2.04	3151	28			48		
9	2.33	2194	29			49		
10	2.62	1649	30			50		
11	2.92	1296	31			51		
12	3.21	1075	32			52		
13	3.50	928	33			53		
14	3.79	824	34			54		
15	4.08	766	35			55		
16	4.37	707	36			56		
17	4.67	663	37			57		
18	4.96	648	38			58		
19	5.25	618	39			59		
20	5.54	339	40			60		

GPO 1961 : 07-501065

556

HYDROGRAPH COMPUTATION

SHT. 2-7
FREE BOARDCK JRM
5/66
CK JRM
7/66WATERSHED OR PROJECT LARCHWOOD LAKE STATE NEW YORKSTRUCTURE SITE OR SUBAREA OTSEGO Co.DR. AREA 1.15 SQ. MI. T_c 0.54 HR.RUNOFF CONDITION NO. II ✓RUNOFF CURVE NO. 73 ✓ STORM DISTRIB. CURVE B ✓ HYDROGRAPH FAMILY NO. 1 ✓STORM DURATION 6 HR.RAINFALL: 22.6 x 1.0 POINT 22.6 IN.AREAL 22.6 IN. Q 18.70 IN.COMPUTED T_p 0.54 x 0.7 HR. 0.38 T_o 5.51 HR.. $(T_o + T_p)$: COMPUTED 14.5 ✓ : USED 16 ✓ REVISED T_p 0.344 ✓ $q_p = \frac{484 A}{REV, T_p} = \frac{484 \times 1.15}{16} = 1618$ CFS. $Q_{qp} = 30,257$ CFS. q (COLUMN) = (t/T_p) REV. T_p . q (COLUMN) = $(q_c/q_p) Q_{qp}$

LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS	LINE NO.	t HOURS	q CFS
1	0	0	21	4.54	1422	41		
2	0.23	30	22	4.77	1362	42		
3	0.45	182	23	4.99	1331	43		
4	0.68	454	24	5.22	1301	44		
5	0.91	817	25	5.45	1210	45		
6	1.14	1120	26	5.68	1029	46		
7	1.36	1422	27	5.90	605	47		
8	1.59	1876	28	6.13	242	48		
9	1.82	2784	29	6.36	121	49		
10	2.04	6745	30	6.58	61	50		
11	2.27	9349	31	6.81	30	51		
12	2.50	7352	32	7.04	0	52		
13	2.72	5174	33			53		
14	2.95	3752	34			54		
15	3.18	2935	35			55		
16	3.41	2451	36			56		
17	3.63	2118	37			57		
18	3.86	1846	38			58		
19	4.09	1668	39			59		
20	4.31	1513	40			60		

LARCHWOOD LAKE

SHT. 3-2


Map Scale - 1" = 100' Planimeter Set At 440.00

1/ Acres = Planimeter Reading $\times 0.230 \times 0.00385$ = Planimeter Reading $\times 0.000888$

Page 2 of 2

GENE ZGEN
MIL ... S. A.

40R- 1ETZ 3RAP - 2ER
10 x 12 PEN INCH



STATE <u>NEW YORK</u>		PROJECT <u>LARCHWOOD LAKE</u>		OTSEGO S.W.C.D.	
BY <u>RKL</u>	DATE <u>7/66</u>	CHECKED BY	DATE	JOB NO. <u>NY-936-P</u>	
SUBJECT <u>DETERMINATION OF EMERGENCY SPILLWAY ELEVATION</u>				SHEET <u> </u> OF <u>3-5</u>	

NORMAL WATER LINE SET AT ELEVATION ^{102.0}~~106.0~~ BY REQUEST OF OWNER

CREST OF EMERGENCY SPILLWAY

REQUIRED STORAGE = 162 AC.FT (SEE PSMC ROUTING)

FROM STAGE STORAGE CURVE SET CREST AT ELEV. 108.56

LARCHWOOD LAKE

SHT. 4-1

DISCHARGE CONSTANTS

<u>WEIR FLOW</u>					30" I.D. R/C PIPE				
$Q = CLH^{3/2}$					2.5' X 7.5' CONCRETE RISER				
$Q = 3.1(13.0)H^{3/2}$					ANTI-VORTEX WALLS AS				
$Q = 40.3 H^{3/2}$					SHOWN ON ES-151 W/CENTERWALL				
					$L = 2(3D-1) = 2(7.5-1) = 13.0'$				
					NOTE: SPLITTER WALL WAS				
					USED, 13.0' IS CORRECT				
<u>PIPE FLOW</u>					30" I.D. R/C PIPE				
$Q = CA\sqrt{2gh}$					$A = 4.91 \text{ sq ft}$				
$C = \frac{L}{\sqrt{1 + K_e + K_p L_p}}$					$L_p = 110 \text{ ft}$				
$= \frac{L}{\sqrt{1 + 1.0 + .00786(110)}}$					$n = .012'$				
$= \frac{L}{\sqrt{12.865}} = \frac{L}{3.587}$					$K_p = .00786' (ES.42 NBH-5)$				
$= .592'$					$K_e = 1.0$				
$Q = .592(4.91)(2.03)h^{1/2}$									
$= 23.31 h^{1/2}$									

SHT. 4-2


$n = 0.40$ $S_e = 0.020'$ $L_e = 200'$ $Control/Sect - 50'$

$$b = 85'$$

Reference ES-124 sheet 28 of 52
ES 139 sheet 1 of 1

U. S. GOVERNMENT PRINTING OFFICE : 1959 O - 507093

Em Spillway Discharge



K-E SEMI-LOGARITHM 46 5493
 5 CYCLES X 70 DIVI IS MADE IN U.S.A.
 KEUFFEL & ESSER CO.

H_p (ft) D-19

5-260 100,000 P. 2/1/60

Stn. H.	Elev. (ft.)	Dist. (ft.)		Area (sq. ft.)		Vol. (cu. ft.)		Total (cu. ft.)
		1st	2nd	1st	2nd	1st	2nd	
100	102	0	0	0.0	15 3.87	90.23	-	0.0
	102.5	0.5	1354	14.2	15 3.87	91.77	-	14.2
	103	1.0	1300	40.3	16 4.00	93.24	-	40.3
	103.5	1.5	1257	74.0	16 4.06	94.69	-	74.0
	104	2.0	1220	113.99	17 4.12	96.11	-	96.11
	104.5	2.5	1183	159.3	17 4.15	97.51	-	97.51
	105	3.0	1146	209.4	18 4.24	98.90	-	98.90
	105.5	3.5			18 4.20	100.26	-	100.26
	106	4.0			18 4.24	101.61	-	101.61
	106.5	4.5			18 4.42	102.93	-	102.93
	107	5.0			20 4.47	104.25	-	104.25
	107.5	5.5			20 4.53	105.54	-	105.54
	108	6.0			21 4.58	106.82	-	106.82
	108.3				21 4.62	107.53	-	107.53
Emer. Spillway Crest	108.6				21 4.65	108.34	0	108.34
	109.0				22 4.69	109.3	4 270	149.3
	109.6				22 4.75	110.7	10 150	200.7
	110.1				23 4.81	112.1	15 309	416.1
	110.4				24 4.84	113.3	20 54	593.3
	111.1				24 4.91	114.5	25 33	814.5
	111.6				24 4.96	115.4	30 117	1095.6
	112.1				25 5.07	116.8	35 155	1356.8
	113.1				26 5.11	119.1	45 250	2176.1
Top of Dam	114.1				21 5.21	121.4	55 340	3071.4

Sta.	Time	Lat.	Long.	Alt.	Temp.	Wind	Clouds	Remarks
1.	1000	30 15	110 00	1000	1000	-	-	200
	1005	30 15	110 00	1000	1000	-	-	200
	1010	30 15	110 00	1000	1000	-	-	200
	1015	30 15	110 00	1000	1000	-	-	200
	1020	30 15	110 00	1000	1000	-	-	200
	1025	30 15	110 00	1000	1000	-	-	200
	1030	30 15	110 00	1000	1000	-	-	200
	1035	30 15	110 00	1000	1000	-	-	200
	1040	30 15	110 00	1000	1000	-	-	200
	1045	30 15	110 00	1000	1000	-	-	200
	1050	30 15	110 00	1000	1000	-	-	200
	1055	30 15	110 00	1000	1000	-	-	200
	1100	30 15	110 00	1000	1000	-	-	200
	1105	30 15	110 00	1000	1000	-	-	200
	1110	30 15	110 00	1000	1000	-	-	200
	1115	30 15	110 00	1000	1000	-	-	200
	1120	30 15	110 00	1000	1000	-	-	200
	1125	30 15	110 00	1000	1000	-	-	200
	1130	30 15	110 00	1000	1000	-	-	200
	1135	30 15	110 00	1000	1000	-	-	200
	1140	30 15	110 00	1000	1000	-	-	200
	1145	30 15	110 00	1000	1000	-	-	200
	1150	30 15	110 00	1000	1000	-	-	200
	1155	30 15	110 00	1000	1000	-	-	200
	1200	30 15	110 00	1000	1000	-	-	200
	1205	30 15	110 00	1000	1000	-	-	200
	1210	30 15	110 00	1000	1000	-	-	200
	1215	30 15	110 00	1000	1000	-	-	200
	1220	30 15	110 00	1000	1000	-	-	200
	1225	30 15	110 00	1000	1000	-	-	200
	1230	30 15	110 00	1000	1000	-	-	200
	1235	30 15	110 00	1000	1000	-	-	200
	1240	30 15	110 00	1000	1000	-	-	200
	1245	30 15	110 00	1000	1000	-	-	200
	1250	30 15	110 00	1000	1000	-	-	200
	1255	30 15	110 00	1000	1000	-	-	200
	1300	30 15	110 00	1000	1000	-	-	200
	1305	30 15	110 00	1000	1000	-	-	200
	1310	30 15	110 00	1000	1000	-	-	200
	1315	30 15	110 00	1000	1000	-	-	200
	1320	30 15	110 00	1000	1000	-	-	200
	1325	30 15	110 00	1000	1000	-	-	200
	1330	30 15	110 00	1000	1000	-	-	200
	1335	30 15	110 00	1000	1000	-	-	200
	1340	30 15	110 00	1000	1000	-	-	200
	1345	30 15	110 00	1000	1000	-	-	200
	1350	30 15	110 00	1000				

STATE <u>New York</u>		PROJECT <u>Larch Wood Lake</u>		SHEET <u>4-5</u>	
BY	DATE	CHECKED BY	DATE	JOB NO.	
SUBJECT <u>Em. Spillway Exit Slope + Velocity</u>				SHEET <u> </u> OF <u> </u>	

Exit Slope

$$Q_{ToTa} = 856 \text{ cfs}$$

$$Q_{pipe} = 115 \text{ cfs}$$

$$Q_m = Q_{ToTa} - Q_{pipe} = 856 - 115 = 741 \text{ cfs}$$

$$25\% \frac{Q}{b} = .25 \left(\frac{741}{85} \right) = 2.18 \text{ cfs}$$

$$\text{Exit Slope} = 0.029$$

Exit Channel Velocity

$$Q_m = 741 \text{ cfs}$$

$$Q/b = \frac{741}{85} = 8.72$$

$$V_c = 6.6 \text{ fps}$$

STATE NEW YORK PROJECT Larchwood Lake
 BY JSH DATE 7/66 CHECKED BY _____ DATE _____ JOB NO. NY-
 SUBJECT DURATION OF FLOW THROUGH EMERGENCY SPILLWAY OF 5-1

Q = Runoff = 0.57 inches

A = Drainage Area = 735 acres

Qp = Pipe Flow at D.H.W. = 115 cfs.

Qem = Emergency Spillway Flow at D.H.W. = Qtotal - Qp = 856 - 115 = 741 cf

To = 1.83 hrs. (Time at which emergency spillway begins to flow)

Ti = 3.65 hrs. (Time at which emergency spillway flow is maximum)

So = 138 ac.ft. (Storage at time To)

Smax = 312 ac.ft. (Storage at time Ti)

Qmax = 856 cfs. (Maximum outflow rate which occurs at time Ti)

I_{max} = $\frac{QA}{12} = \frac{0.57 \times 735}{12} = \underline{524.9}$ ac.ft. (Total inflow volume).

I_i = 25.82 sq.in x $\frac{\text{cfs/in of ordinate} \times \text{sec./in of abscissa}}{43,560}$

25.82 x $\frac{400 \times 1800}{43,560} = \underline{419.8}$ ac.ft.

t₁ = Ti - To = 3.65 hrs. - 1.83 hrs. = 1.82 hrs.

t₂ = $\frac{(I_{\text{max}} + S_{\text{max}}) - (I_i + S_o)}{Q_p + 0.3 \cdot Q_{\text{em}}} \times 12.1 = \frac{(524.9 \text{ ac.ft.} + 312.0 \text{ ac.ft.}) - (419.8 \text{ ac.ft.} + 138 \text{ ac.ft.})}{115 \text{ cfs} + 0.3 \times 741 \text{ cfs}} \times 12.1$

= 10.02 hrs.

Duration of Flow = t₁ + t₂ = 1.82 hrs + 10.02 hrs = 11.84 hrs.

STATE NEW YORK		PROJECT LARCHWOOD LAKE		JOB NO. NY-936-P	
BY JH	DATE 6/66	CHECKED BY RKC	DATE 6/66		
SUBJECT DRAWDOWN TIME COMPUTATIONS-				SHEET 5-2	

[illegible]

L Storage above crest of RISER 106.0

$$\frac{2}{\frac{\text{ac. ft.}}{\text{avg. outflow}}} \times 0.504 = \text{Time (in days)}$$

PRELIMINARY GEOLOGIC INVESTIGATION

CHECK LIST

TO DETERMINE THE ADEQUACY OF DAMSITE INVESTIGATIONS

NAME CLAIR JACOBSEN SR-WCD OTSEGO
 Site location 2 MI. N. OF WEST LAURENS Quadrangle MORRIS 7 1/2
 Date 1/17/66 Personnel MULVANEY, FIELD & KICK

ITEM

Are adequate quantities available? YES
 Location U.S.G.S. C.V. Available
EMER. CM-6C
U.S. BORROW CM-6C } 6000 YDS +

Is filter material available at or near the site? PROBABLY NOT
 Material Sample Quantity available

Has each filter embankment material at the site been sampled for complete correlation tests? YES (Soil Correlation Table)

Are water tables located? INDICATED IN LOGS & IN NARRATIVE W/
RESPECT TO DEWATERING CUTOFF TRENCH

Consolidation and shear strength

Can in-place bearing strength be determined? FOUNDATION IS A DENSE

Are water levels and pervious zones shown in logs and on profiles? PARTLY

Has each distinct foundation material been sampled for sieve and/or mechanical (vibrometer) analysis? NO. If not, does report contain correlation evidence to other samples? YES (Soil Correlation Table)
(PARTIALLY)

Have samples for filter design been obtained from the foundation drain location or correlated to other samples taken from the site? NO
 Filter plant Abutments Embankments

Bedrock characteristics (if applicable) N.A.

Weathered (soft)?
 Firm (hard)?
 Bedding thickness?
 Strike and dip?
 Fractures and/or cavity locations and descriptions?
 Water or permeability tests or remarks?
 Confirmation of bedrock or boulders?

Do borings extend to sufficient depth to establish stable and impermeable materials? YES Is proof by test data or samples recorded? BOTH

Are water or permeability tests available or sufficient remarks to determine values by Bur. of Rec. methods, E-18 or E-19, Earth Manual? Or can it be estimated by D_{10} and dry density (Slichter)?

MIN 6% OF FINES = 32%. PERM. NOT A FACTOR
IN EMBA. OR FOUND.
D-25

8. Have zones or areas of critical foundation materials been delineated on the plans? Profiles?

1. Is the found item location adequate? YES Yielding? No
Non-yielding? ESSENTIALLY Is the proof available in test data? LOGS
Samples:

Three test data or samples been obtained to be used to determine loading and elongation. LOADS & REPORT

Have water holes or conditions been located: PARTLY ✓
VIEW. How ABOUT EXCAVATION OF THIS NATI.

1. Do test holes extend to or below proposed splitway grades or elevation? ?

3. Are seepage areas or water levels described and located? NONE INDICATED

Are soils described or sampled to determine erodibility? STAMP 100
 Sample use on embankments? YES

Conclusions, as outlined by this report, indicate the need for a far more detailed investigation and in-place testing.

Further investigation is needed.

B. S. Ellis
Geologist

Preliminary Geologic Investigation

GENERAL

Date of Exploration: 1/17/66
 Personnel: J.R. Mulvaney, F. Fields, L. Kick
 Site Name: Clair Jacobsen Pond
 SWCD: Otsego
 Geographic Location: 2 mi. N. of West Laurens
 Quadrangle: Morris 7 $\frac{1}{2}$ minute
 Equipment: Backhoe
 Site Data: Drainage Area: 600 Ac.
 Max. Pool Depth: 17 feet
 Max. Height of Dam: 24 feet
 Length of dam: 400 feet
 Volume of fill: 6000 cu. yd.(estimate)

EMBANKMENT FOUNDATION

Five test pits were dug along the C/L of the dam. Pit 1 was dug near the upper end of the east abutment, and was sampled at a depth of 7 to 8 feet (Sample 1.1). Pit 4 was dug near the upper end of the west abutment. Both pits were well into dense glacial till. Pits 2 and 5 were a few feet above the stream and showed colluvial material in the upper part, but both were dug well into the same dense glacial till as sampled in pit 1. Pit 3, located in the bottom of the draw, also showed the same dense till below 2 feet depth.

PRINCIPAL SPILLWAY

Pit 301 was dug at the lower end of the principal spillway, and was sampled at the 6 to 7 foot depth (Sample 301.1). Pit 302 was dug at the upper end. Both pits showed good material for footings for the outlet structure in the bottom of the pits.

EMERGENCY SPILLWAY AND BORROW

All or most of the fill will come from excavating the emergency spillway. Pits 201, 202, 203, and 204 were dug in the spillway area, and pit 201 was sampled at the 10 to 12 foot depth. (Sample 201.1). In the event additional borrow is needed, pit 101 was dug and sampled at the 4 to 6 depth. All pits showed a quite uniform, dense, deep till throughout the area, which is usable with a minimum of waste. Clearing is needed.

RECOMMENDATIONS

1. Cutoff trench

A cutoff trench of a minimum 4 feet depth is sufficient for both abutments. Trench will have a 12 foot width with 1:1 side slopes.

2. Principal Spillway

Spillway pipe camber should be considered in design.

3. Drainage

Installation of foundation drains is recommended to insure downstream slope stability.

4. Embankment Design:

The dense glacial till found in the emergency spillway excavation and borrow area is suitable homogeneous embankment material. I recommend that this material be used for backfill of cut off trench and embankment construction with controlled compaction. Sides slope upstream should be 3:1 and downstream $2\frac{1}{2}$:1 with a 8' berm upstream at normal water level.

5. Miscellaneous

Seepage during cutoff trench excavation will be a problem and dewatering will be required. Close attention should be given to sorting out the plus 6 course fragments from the fill material. This appears to be no problem with respect to emergency spillway excavation or the use of this material in the embankment.

670. 40

MSK 9 b

benzylw-dus

Location

Qatar

Watermark

CLARENCE E. FARRUSH

Site No. 1

Pub. 46-

२३

2

Subject: WP1

2961

1

1. *Introduction*

五

2

14

五

10

4

Location of Holes

BACK 40 E

Hole No.	Station and Surface Elev.	Hole Depth		Description of Materials Description at 2 ft intervals	Unif. Soil Class. Symb.	Type Bit Used	Samples					
		From	To				No.	Type	From	To	Rec. %	
501	40.41	0	3	COLLUVIUM - GRAVEL-SILTY QUITE HIGH IN % SILTS	GM							
	42 LT			11/15-20% SUB-ANGULAR CORNERS & SMALL BOUNDER								
	56.250			BROWN-MOIST-MODERATE PERMEABILITY-DEVONIAN								
	56.250			AGE-GLACIAL TILL MEDIUM								
		3	7	SILTY-GRAVEL - 44/20-25% SURROUNDED CORNERS	GM							
				AND BOUNDER > 4" and 5% SUB-ROUND PEBBLES								
				1/4 TO 1/2 - GRAY-MOIST-DEVONIAN AGE-GLACIAL								
				TILL - VERY DENSE								
				(6-7 SAMPLE 501.1)								
										</		

Disturbed-undisturbed-rock core. † Percent sample recovery.
 ‡ Data copy for the New York State Office of Environmental Conservation Laboratory with samples.
 § Other copies as directed by State Conservationist.
 ¶ Other copies as directed by State Conservationist.

Sheet 1 of 1 Subjects

Project No. 19 Date June 29 1968 Locality Sub-watershed State WISCONSIN Site No. 501
 Date June 29 1968 Project WP1 WP2 FP Pub. 46
 Location Sub-watershed Date June 29 1968 Project WP1 WP2 FP Pub. 46
 Drilling Equipment BACKHOF Location of Holes Sub-watershed

Hole No.	Station and Surface Elev.	Hole Depth		Description of Materials	Unif. Soil Class. Symb.	Type Bit Used	Samples			
		From	To				Type	No.	From	To
		Fl.	Fl.						Fl.	Fl.
2-A	95.0	0	2	TOP SOIL						
	15.1	2	4	SILT-GRAVEL-quite high % silt - w/5% sub-ANGULAR STONES (54" and w/5% (24" - BROWN -	GM					
	11.90			MOIST - SLOWLY PERMEABLE - DEVONIAN AGE - GLACIAL TILL - DENSE						
	4.00	4	6	SILTY GRAVEL - quite high % silt & very fine sands GM w/10% sub-founded stones (24" - gray - moist -	GM					
				SLOWLY PERMEABLE - DEVONIAN AGE - GLACIAL TILL - DENSE						
		6	9	GRAVEL - SILTY - w/10% sub-angular stones (24" - 54" -	GM					
				5% (24" - gray - wet to moist - SLOWLY PERMEABLE - DEVONIAN AGE - GLACIAL TILL - DENSE	GM					
				* SLOW SEEPAGE AT 7 FEET - IN A GRAVEL -						
				PUCKET OF MODERATE PERMEABILITY - THIS						
				SEEPAGE APPEARS TO BE AT SOME LEVEL						
				ABOVE THE STREAMBED.						

Disturbed - undisturbed rock core. * Percent sample recovery. 1 copy to E and WP Unit, 1 copy Soil Mechanics Laboratory with samples. Other copies as directed by State Conservationist.

Location of Holes

Sheet _____ of _____ Sheets
Sheet _____ of _____ Sheets

D-34

ЖУРНАЛ

СЛУЖБА ЗАКОПАН

N. J. M. Co., N. J.

21. M. of M. Luens, Osego Co.

Watershed Saquehanna Sub-watershed

Logged by L. Kick

Drilling Equipment Backhoe

Description of Materials

Location of Holes

[illegible]Sheet of Sheets

• Disturbed-undisturbed-rock core. † Percent sample recovery.
1 copy to E and WP Unit, 1 copy Soil Mechanics Laboratory with samples.
Other copies as directed by State Conservationist. 27 5

CURVE ADJUSTED TO REFLECT 4.5% + 3 MATERIAL

SITE New York		PROJECT Larchwood Lake	
DATE 8/66	CHECKED BY	DATE	JOB NO. NY-936-D
Placement of Fill Material			SHEET OF

Homogeneous Fill

Earth Fill shall be from material in the emergency spillway and supplemental borrow area represented by TP 101 from 1'-6"; TP 201 1'-12"; and TP 202 from 2'-8".

The coarsest material shall be placed in the outer most portion of the dam as directed by the engineer.

Max. rock size = 6"

Max. lift = 9"


Req'd Water Content = 2 per centage points less to 2 per centage points greater than optimum.

Class A Compaction


95% max. density by ASTM D698, Method A

SOILS ANALYSES

MATERIALS TESTING REPORT		U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE		SOIL CLASSIFICATION	
PROJECT and STATE JACOBSEN POND, OTSEGO CO., N.Y.				SAMPLE LOCATION BORROW	
FIELD SAMPLE NO. 101.1		DEPTH 4'-6'		GEOLOGIC ORIGIN	
TYPE OF SAMPLE DIST. 35 LB.		TESTED AT SCS LAB-SYR., N.Y.		APPROVED BY	
SYMBOL GM-GC		DESCRIPTION		DATE 5-19-66	




MATERIALS TESTING REPORT		U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE		COMPACTION AND PENETRATION RESISTANCE	
PROJECT OR DATE JACOBSEN POND, OTSEGO CO., N.Y.					
FIELD SAMPLE NO. 101.1		LOCATION BORROW		DEPTH 4'-6'	
GEOLOGIC FORM		TESTED AT SCS LAB-SYR, NY		APPROVED BY DATE 5-66	
CLASSIFICATION GM-GC		L. 23		PI 5	
MAX. PARTICLE SIZE INCLUDED IN TEST #4		CURVE NO. 1		OF 2	
SPECIFIC GRAVITY (G _s)		STC (ASTM D-698) <input checked="" type="checkbox"/> METHOD A		MOD (ASTM D-557) <input type="checkbox"/> METHOD	
{ MINUS NO. 4 PLUS NO. 4		MOD (ASTM D-557) <input type="checkbox"/> METHOD		OTHER TEST <input type="checkbox"/> (SEE REMARKS)	




REMARKS

MATERIALS TESTING REPORT		U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE		SOIL CLASSIFICATION	
PROJECT and STATE JACOBSEN POND, OTSEGO CO., N.Y.				SAMPLE LOCATION PR. SPLWY	
FIELD SAMPLE NO. 301.1		DEPTH 6'-7'		GEOLOGIC ORIGIN	
TYPE OF SAMPLE DIST. 35 LB.		TESTED AT SCS LAB-SYR., N.Y.		APPROVED BY	
SYMBOL GM		DESCRIPTION			
		DATE 5-19-66			



MATERIALS TESTING REPORT		U. S. DEPARTMENT of AGRICULTURE SOIL CONSERVATION SERVICE		SOIL CLASSIFICATION	
PROJECT and STATE JACOBSEN POND, OTSEGO CO., N.Y.				SAMPLE LOCATION EM. SPLWY	
FIELD SAMPLE NO 201.1	DEPTH 8'-10'	GEOLOGIC ORIGIN			
TYPE OF SAMPLE DIST. 35 LB.		TESTED AT SCS LAB-SYR., N.Y.		APPROVED BY DATE 5-19-66	
SYMBOL GM - GC		DESCRIPTION			



MATERIALS	U. S. DEPARTMENT OF AGRICULTURE	COMPACTION AND
TESTING REPORT	SOIL CONSERVATION SERVICE	PENETRATION RESISTANCE

201.1	EM. SPLWY	8'-10'
-------	-----------	--------

201.1

EM. SPLWY

8'-10'

SCS LAB-SYR.N.Y.


5-66

CLASSIFICATION GM-GC - 26 - 6 - PAGE NO 2 OF 2

MAX. PARTICLE SIZE INCLUDED IN TEST 4 STD ASTM D-698, X METHOD A

MINUS NO 4 MOD (ASTM D 557) METHOD

SPECIFIC GRAVITY (G _s)	PLUS NO. 4	OTHER TESTS	SEE REMARKS
------------------------------------	------------	-------------	-------------

[illegible]

MATERIALS U.S. DEPARTMENT OF AGRICULTURE
TESTING REPORT SOIL CONSERVATION SERVICE

SOIL CLASSIFICATION

PROJECT OR STATE

SAMPLE LOCATION

JACOBSEN POND OTSEGO CO., N.Y.

Q PR. SPLWY

FIELD SAMPLE NO.

LABORATORY NO.

302-A1

DATE

TESTED BY

APPROVED BY

DATE

DIST

SCS LAB-SYR., N.Y.

7-16-66

SYMBOL

DESCRIPTION

DEPTH (inches)	MOISTURE (%)	TEMPERATURE (°C)	WATER POTENTIAL (cm)	PERCENTAGE (%)	REMARKS
0-1					
1-2					
2-3					
3-4					
4-5					
5-6					
6-7					
7-8					
8-9					
9-10					
10-11					
11-12					
12-13					
13-14					
14-15					
15-16					
16-17					
17-18					
18-19					
19-20					
20-21					
21-22					
22-23					
23-24					
24-25					
25-26					
26-27					
27-28					
28-29					
29-30					
30-31					
31-32					
32-33					
33-34					
34-35					
35-36					
36-37					
37-38					
38-39					
39-40					
40-41					
41-42					
42-43					
43-44					
44-45					
45-46					
46-47					
47-48					
48-49					
49-50					
50-51					
51-52					
52-53					
53-54					
54-55					
55-56					
56-57					
57-58					
58-59					
59-60					
60-61					
61-62					
62-63					
63-64					
64-65					
65-66					
66-67					
67-68					
68-69					
69-70					
70-71					
71-72					
72-73					
73-74					
74-75					
75-76					
76-77					
77-78					
78-79					
79-80					
80-81					
81-82					
82-83					
83-84					
84-85					
85-86					
86-87					
87-88					
88-89					
89-90					
90-91					
91-92					
92-93					
93-94					
94-95					
95-96					
96-97					
97-98					
98-99					
99-100					

501.1

MATERIALS TESTING REPORT SOIL CONSERVATION SERVICE

SOIL CLASSIFICATION


JACOBSEN POND OTSEGO CO., N.Y.

SOIL

DIST. SCS LAB-SYR., N.Y.

7-16-66

0015 0019 0048 05 1.0 25.0 75.0 66.6 .08



STRUCTURAL CALCULATIONS

STATE NEW YORK		PROJECT LARCHWOOD LAKE			JOB NO. NY-936P	
BY DCZ	DATE 7/66	CHECKED BY	DATE			
SUBJECT RISER LOAD COMPUTATION					SHEET 1 OF 1-1	

$f_s = 140$ p.c.f. (this value is considered conservative)

$f_b = 140 - 62.4 = 77.6$ p.c.f.

Assume $K = 0.55$

$\therefore f = 0.55(77.6) = 42.7$

$f_{\text{effective}} = 42.7 + 62.4 = 105.1$ p.c.f.

T.R. 30 Pg. 1-2 $K_{wb} = 45$ pcf $\therefore f = 45 + 62.4 = 107.4$ p.c.f.

\therefore Design Loading is adequate.

STATE NEW YORK		PROJECT LARCHWOOD LAKE		JOB NO. NY-936 P
BY D.C.Z	DATE 7/66	CHECKED BY L.C.I	DATE 8/2/66	
SUBJECT Conduit Loading Calculations				SHEET 1 OF 2 2-1

EARTH FILL :

Embankment material is a dense glacial fill & homogeneous.

$$f = 140 \text{ */cu. FT. (Assumed)}$$

$$\phi = 32^\circ \text{ assumed based on GM-GC}$$

$$\text{Wall Thickness} = 3.12''$$

Type B-1 Concrete Bedding

Classify as a positive projecting
(Refer to SCS-442) Conduit
27 Rev)

1- Sub-classify as complete or incomplete

$$p = \frac{pb_c}{b_c} = \frac{3.35}{3.02} = 1.11$$

$$S = 1.0 \quad (\text{ES-115 sheet 2 of 4 - Assume Case a})$$

$$\phi_p = 1.0 \times 1.11 = 1.11$$

$$K_\mu = 0.19 \quad (\text{ES-114 sheet 3 of 3})$$

$$\frac{H_c}{b_c} = 2.10 \quad (\text{ES-117 sheet 1 of 2})$$

$$\frac{H_c}{b_c} = \frac{30.0}{25.85} = \frac{9.93}{8.60}$$

$$\frac{H_c}{b_c} > \frac{H_c}{b_c} \therefore \text{INCOMPLETE Condition Exists}$$

2- Obtain C_p (ES-118 sheet 2 of 3)

$$2K_\mu \frac{H_c}{b_c} = 2 \times 0.19 \times \frac{9.93}{8.60} = 3.77$$

$$2K_\mu \phi_p = 2 \times 0.19 \times 1.11 = 0.422$$

$$2K_\mu C_p = \frac{7.80}{6.7} \quad C_p = \frac{7.80}{2K_\mu} = \frac{7.80}{2 \times 0.19} = \frac{20.53}{17.63}$$

(ES-118 2 of 3)

STATE <u>NEW YORK</u>		PROJECT <u>LARCHWOOD LAKE</u>		
BY <u>DCZ</u>	DATE <u>7/66</u>	CHECKED BY <u>LCI</u>	DATE <u>8/2/66</u>	JOB NO. <u>NY-936 P</u>
SUBJECT <u>Conduit Loading Calculations</u>				SHEET <u>2</u> OF <u>2</u> <u>22</u>

3 - Solve for W_c

$$W_c = C_p j b_c^2 = \frac{20.66}{17.63} \times 140 \times (3.02)^2 = \frac{26,380}{22,514} \text{ #/L.F. of conduit}$$

4 - Solve for K_t

$$K = \frac{0.31}{0.27} \quad (\text{ES-114 Sheet 3 of 3})$$

$$K_t = \frac{PK}{C_p} \left(\frac{H_c}{b_c} + \frac{P}{2} \right) = \frac{1.0 \times 0.27}{\frac{17.63}{20.66}} \left(\frac{9.93}{2.60} + \frac{1.0}{2} \right) = 0.127$$

5 - Obtain X_p (ES-120 sheet 3 of 5 for type B+ Concrete Bedding)

$$X_p = 0.650$$

6 - Obtain X_a (ES-120 sheet 5 of 5)

$$\text{Use } \rho = 1.0$$

$$X_a = 0.638$$

7 - Solve for L_f

$$L_f = \frac{1.431}{X_p - K_t X_a} = \frac{1.431}{0.650 - (0.127)(0.638)} = \frac{2.60}{2.55}$$

8 - Solve for R_{eb}

$$R_{eb} (\text{Prestressed } -0.001 \text{ crack}) = \frac{W_c}{L_f} = \frac{\frac{26,380}{22,514}}{\frac{2.55}{2.60}} = \frac{10,146}{8,829} \text{ #/L.F.}$$

— Pressure Head = 25 FT.

— Load (W_c) = $\frac{26,380}{22,514}$ #/LN.FT. based on O.D. of 3.02' (Reference - Lock Joint SP-12 PIPE)


— Min. 3 edge bearing for 0.001" crack

$$R_{eb} (\text{Prestressed Pipe}) = \frac{10,146}{8,829} \text{ #/LN.FT. (AWWA C-301)}$$

MAX strength for SP-12 = 10,000 #/L.F.

K-2 10 X 10 IN. (INCH) 46 0103
7 X 10 INCHES
MADE IN U.S.A.
KEUFFEL & ASSOCIATES

LARCHWOOD LAKE STILLING BASIN CUT.



STATE <u>NEW YORK</u>		PROJECT <u>LARCHWOOD LAKE</u>		
BY <u>J.F.P.</u>	DATE <u>7/12/66</u>	CHECKED BY <u>D.C.2</u>	DATE <u>7/66</u>	JOB NO. <u>N.Y.-936-D</u>
SUBJECT <u>OUTLET CHANNEL VELOCITY - PRINCIPAL SPILLWAY</u>				SHEET <u> </u> OF <u>4-1</u>

$$\begin{aligned}
 Q &= 115 \text{ CFS} \\
 n &= 0.035 \\
 b &= 10.0 \text{ ft} \\
 S &= 0.0025 \text{ ft/ft} \\
 S.S. &= 2:1
 \end{aligned}$$

$$Q = \frac{K'}{n} b^{5/2} S^{1/2}$$

$$K' = \frac{Qn}{b^{5/2} S^{1/2}} = \frac{115 \times 0.035}{(10)^{5/2} \times (0.0025)^{1/2}} = \frac{115 \times 0.035}{164 \times 0.05} = \frac{4.025}{23.2}$$

$$K' = 0.173$$

FROM TABLE 7-11, PAGE 7-38 OF KING'S HANDBOOK OF HYDRAULICS

$$\frac{D}{b} = 0.25$$

$$D = 0.25 \times 10.0 = 2.50 \text{ ft.}$$

$$D = 2.5'$$

$$r = 1.77$$

$$V = 1.78 \text{ f.p.s.} \quad V = 3.01 \text{ f.p.s.}$$

DAM CONSTRUCTION PERMIT APPLICATION

STATE OF NEW YORK
WATER RESOURCES COMMISSION
CONSERVATION DEPARTMENT
ALBANY, N.Y. 12226

WRC FORM #2 1/66

Do Not Write in This Box

Appl. No. 7-0-66-66
Permit No. _____

Dam No. 130C-3588
Watershed Susquehanna River

Application for a Permit for the Construction, Reconstruction or Repair of a Dam
or Other Impoundment Structure under Conservation Law, Section 429(c).

INSTRUCTIONS

1. Type or print name.
2. All papers must be filed in quadruplicate.
3. The completed application relating to construction, reconstruction or repair of a dam must include the following information:
 - (a) A topographical plan (with contours) of the impounded area drawn to a suitable scale.
 - (b) A profile and transverse section of the impounded area showing the proposed excavation, the normal water and possible high water elevations. A 1'-0" minimum of freeboard is to be provided between the top of the dam and the possible high water.
 - (c) A longitudinal elevation and transverse section of the dam with all the necessary details of the related appurtenances, spillways, drains, etc.
 - (d) A log of the soil information. Samples of the materials to be used in the dam and of the material upon which the dam is to be founded may be asked for, but need not be furnished unless requested.
4. No work of construction, reconstruction or repairs of the structure or structures shall be started until a permit therefor has been issued by the New York State Water Resources Commission.
5. The design, preparation of plans, estimates and specifications and the supervision of the erection, reconstruction and repair of all the structures herein applied for shall be done by a licensed professional engineer, or in the case of farm ponds by an engineer or conservationist employed by a governmental agency cooperating with a soil conservation district, or by an engineer employed by the Conservation Department.
6. A "Notice of Application" must be published by the applicant. The form of notice and instructions for publication will be furnished to the applicant by the Local Permit Agent to whom the application is delivered.

APPLICATION

Application is hereby made by (Clair Jackson) Larchwood Lake
to the Conservation Department acting on behalf of the Water Resources Commission, pursuant to the provisions of Conservation Law, Section 429(c) for a permit to (construct) (~~reconstruct~~) (~~repair~~) a dam or impoundment structure substantially as shown on plans and specifications marked N.Y. 936-P herewith submitted and described.

It is intended to commence the work covered by the application
about Aug 1966 (Date) and complete it about Nov. 1967 (Date)

1. The dam will be on Butts Corner Creek flowing into Wharton Creek
in the town of Laurens County of Olsego and
1.3 mi N.W. of Butts Corner
(Give exact distance and direction from a well-known bridge, dam, village, main cross-roads or mouth of a stream)

2. Location of dam is shown on the attached map or overlay of the Morris N.Y. quadrangle
of the United States Geological Survey at latitude 42° 33' 00" longitude 75° 16' 02"

3. The impounded water will be used for Recreation

4. Will any part of the dam be built upon or its pond flood any State lands? No.

5. The area draining into the proposed pond or lake is 735 acres; 1.15 square miles.

6. The computed 6.57 year peak rate of runoff used in the design is 4078 cu. ft. per sec. State criterion
or method used in determining the peak rate of runoff U.S.O.A. Soil Cons. Serv. Engineers Hdbk #4 - Soil Conserv. Complex

7. The maximum height of the proposed dam above the bed of the stream will be 27 feet - inches.

8. The designed maximum high water elevation above the spillcrest is computed to be 2.6 feet - inches;
the designed freeboard as measured from the maximum high water elevation to the top of the proposed dam will be 2.7 feet - inches. (One foot minimum)

9. The open spillway of the proposed dam that will control the designed flood flow will be of

Vegetated earth Spillway
(State type, such as: vegetated earth, concrete, masonry, timber, rock filled crib, etc.)

The width of the control section of the spillway, measured normal to the flow of water at the crest, will be 85 feet

Bank inches in the clear; facing down stream, the waters will be held at the right end by a Natural

the top of which will be - feet - inches above the spillcrest.

and have a top width of - feet - inches; and at the left end by Natural Bank & Ridge

the top of which will be 5.5 feet - inches above the spillcrest and have a top width of 14

feet - inches. The slope of the sides of the spillway will be 3 on 1 (left)

(right)

INSTRUCTIONS

1. Type or print in ink.
2. All papers must be filed in quadruplicate.
3. The completed application relating to construction, reconstruction or repair of a dam must include the following information:
 - (a) A topographical plan (with contours) of the impounded area drawn to a suitable scale.
 - (b) A profile and transverse section of the impounded area showing the proposed excavation, the normal water and possible high water elevations. A 1'-0" minimum of freeboard is to be provided between the top of the dam and the possible high water.
 - (c) A longitudinal elevation and transverse section of the dam with all the necessary details of the related appurtenances, spillways, drains, etc.
 - (d) A log of the soil information. Samples of the materials to be used in the dam and of the material upon

which the dam is to be founded may be asked for, but need not be furnished unless requested.

4. No work of construction, reconstruction or repairs of the structure or structures shall be started until a permit therefor has been issued by the New York State Water Resources Commission.
5. The design, preparation of plans, estimates and specifications and the supervision of the erection, reconstruction and repair of all the structures herein applied for shall be done by a licensed professional engineer, or in the case of farm ponds by an engineer or conservationist employed by a governmental agency cooperating with a soil conservation district, or by an engineer employed by the Conservation Department.
6. A "Notice of Application" must be published by the applicant. The form of notice and instructions for publication will be furnished to the applicant by the Local Permit Agent to whom the application is delivered.

APPLICATION

Application is hereby made by (Clair Jacobson) Larchwood Lake to the Conservation Department acting on behalf of the Water Resources Commission, pursuant to the provisions of Conservation Law, Section 429(c) for a permit to (construct) (~~reconstruct~~) (~~repair~~) a dam or impoundment structure substantially as shown on plans and specifications marked N.Y. 936-P herewith submitted and described.

It is intended to commence the work covered by the application

about Aug 1966 (Date) and complete it about Nov. 1967 (Date)

1. The dam will be on Butts Corner Creek flowing into Wharton Creek in the town of Lawrence County of Otsego and 1.3 mi N.W. of Butts Corner

(Give exact distance and direction from a well-known bridge, dam, village, main cross-roads or mouth of a stream)

2. Location of dam is shown on the attached map or overlay of the Morris, N.Y. quadrangle of the United States Geological Survey at latitude 42° 33' 00" longitude 75° 16' 02"

3. The impounded water will be used for Recreation

4. Will any part of the dam be built upon or its pond flood any State lands? No.

5. The area draining into the proposed pond or lake is 735 acres; 1.15 square miles.

6. The computed 8.57 year peak rate of runoff used in the design is 4078 cu. ft. per sec. State criterion or method used in determining the peak rate of runoff U.S.O.A. Soil Cons. Serv. Engineers Hobb #4 - Soil Conserv. Complex

7. The maximum height of the proposed dam above the bed of the stream will be 27 feet - inches.

8. The designed maximum high water elevation above the spillcrest is computed to be 2.6 feet - inches; the designed freeboard as measured from the maximum high water elevation to the top of the proposed dam will be 2.9 feet - inches. (One foot minimum)

9. The open spillway of the proposed dam, that will control the designed flood flow will be of

Vegetated earth Spillway

(State type, such as: vegetated earth, concrete, masonry, timber, rock filled crib, etc.)

The width of the control section of the spillway, measured normal to the flow of water at the crest, will be 85 feet

Bank inches in the clear; facing down stream, the waters will be held at the right end by a Natural

Bank the top of which will be - feet - inches above the spillcrest, and have a top width of - feet - inches; and at the left end by Natural Bank + Pond

the top of which will be 5.5 feet - inches above the spillcrest and have a top width of 14 feet - inches. The slope of the sides of the spillway will be 3 on 1 (left)

3 on 1 (right).

10. The spillway is designed to safely discharge 875 cu. ft. per sec.

11. The surface area of the proposed pond or lake will be 59 acres at the normal water elevation and 74 acres at the spillcrest elevation; the volume of the water impounded in the pond or lake will be 19,223,911 gallons at the normal water elevation and 27,113,466 gallons at the spillcrest elevation.

12. The normal water elevation of the proposed pond or lake will be 2.6 feet - inches below the spillway crest, and will be maintained by means of a Reinforced Concrete Drop outlet; the pond or lake will be drained by means of a 12" diam. C.T.P. provision will be made for supplying water to riparian owners downstream, during dry seasons, by means of 12" slide gate.

13. The maximum discharge through the spillway that controls the normal water elevation will be 114 cu. ft. per sec. during maximum high water.

N.A. 14. If flashboards are to be used to control flood flow they must be of the automatic or self-tilting type, designed to fail or otherwise permit full discharge through the spillway when the flood waters reach a height of _____ feet _____ inches above the spillcrest.

N.A. 15. If an overfall structure is used as a spillway, it shall be provided with an apron constructed of _____; the thickness of the _____ will be _____ feet _____ inches, the width _____ feet _____ inches across the stream and the length _____ feet _____ inches parallel to the stream.

16. Facing downstream, what is the nature of material composing the right bank? gravel, silty moderately permeable - glacial till

17. Facing downstream, what is the nature of the material composing the left bank? gravel, silty with sand, massive, slowly permeable, glacial till

18. The natural material of the bed on which the proposed dam will rest is (clay, sand, gravel, boulders, granite, shale, slate, limestone, etc.) gravel, silty, slowly permeable, glacial till

19. Are there any porous seams or fissures beneath the foundation of the proposed dam? no

20. State the character of the bed and the banks in respect to the hardness, perviousness, water bearing, effect of exposure to air and to water, uniformity, etc. Material is slow to moderately permeable, firm in place, uniformly dense, glacial till.

21. Was the above soil information obtained from soil borings? _____; test pits? _____

22. State the height above the spillcrest elevation of the lowest part of the immediate upstream adjoining property or properties, _____ feet _____ inches. flooded rights obtained by owner

23. Does this proposed pond or lake constitute any part of a public water supply? no If not, where is the nearest downstream public water supply intake located? unknown

24. State if any damage to life or to any buildings, roads or other property could be caused by any possible failure of the proposed dam possible damage to life, buildings & County road 1 1/2 to 1 3/4

25. The design, plans and specifications have been prepared under the supervision of me from site to U.S.D.A. Soil Conserv. Serv. or P.E. License No. _____ near Butts Corners
(Authorized Agency)

Address 700 E. Water St. Syracuse N.Y. Title State Conservation Engineer

26. The Erection will be under the supervision of
(State which: Erection, Reconstruction or Repairs)

U.S.D.A. Soil Conserv. Serv. or P.E. License No. _____
(Authorized Agency)

Address 139 Main St. Cooperstown, N.Y. Title Work Unit Conservationist

27. Name and address of official newspaper of the town or city in which the proposed works are to be located,

Ontario Star, Ontario, N.Y.

All provisions of law will be complied with in the erection and maintenance of the proposed dam or impoundment structure. The construction will be carried out substantially in accordance with the approved plans and specifications.

If the applicant is other than the owner, the applicant certifies that he has been duly authorized by the owner to make the application and to carry out the project described herein.

The applicant certifies the truth of the above statements and agrees that the issuance of the permit is based on the accuracy thereof. As a condition to the issuance of a permit, the applicant accepts full legal responsibility for all damage, direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and agrees to indemnify and save harmless the State from suits, actions, damages and costs of every name and description resulting from the said project.

Clair Jacobsen, Owner

By _____, authorized agent of owner.

Address of owner New Berlin, N.Y.

Address of signer _____ Date Aug 15, 1966
(If other than owner)

NOTE: Acceptance of a permit subjects permittee to restrictions, regulations or obligations stated in application and permit.

DAM CONSTRUCTION PERMIT

PERMIT NO. 7-66-66
 DAM NO. 130C-3588
Susquehanna River

STATE OF NEW YORK
 WATER RESOURCES COMMISSION
 CONSERVATION DEPARTMENT

CLAIR JACOBSEN residing at
New Berlin, New York
 is hereby permitted to: (construct) (reconstruct) (repair) (alter the bed or banks of) (dredge) (place fill in) _____
A Pond
 Located in County Onesago Town Laurens by
 carrying out the following works: Construct an earth fill dam with vegetated spillway according
to Soil Conservation Service plans # NY 936-P and specifications attached thereto

Section of stream to which this permit applies Butts Corner's Creek, tributary of Wharton Creek,
1.3 miles northwest of Butts Corners

Note: (a) This permit does not relieve the permittee of responsibility for damages to riparian owners or others.

(b) If the structure or work herein authorized is not completed on or before 31st day of
December, 1967, this permit, if not specifically extended, shall cease and be null and void.

CONDITIONS

1. The permitted work shall be subject to inspection by an authorized representative of the Water Resources Commission who may order the work suspended if the public interest so requires.

2. The permittee shall file in the office of the Local Permit Agent a notice of intention to commence work at least 48 hours in advance of the time of commencement and shall also notify him promptly in writing of the completion of the work.

3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages, direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to indemnify and save harmless the State from suits, actions, damages and costs of every name and description resulting from the said project.

4. Any material dredged in the prosecution of the work herein permitted shall be removed evenly, without leaving large refuse piles, ridges across the bed of the waterway, or deep holes that may have a tendency to cause injury to navigable channels or to the banks of the waterway.

5. Any material to be deposited or dumped under this permit, either in the waterway or on shore above high-water mark, shall be deposited or dumped at the locality shown on the drawing hereto attached, and, if so prescribed thereon, within or behind a good and substantial bulkhead or bulkheads, such as will prevent escape of the material into the waterway.

6. There shall be no unreasonable interference with navigation by the work herein authorized.

7. That if future operations by the State of New York require an alteration in the position of the structure or work herein authorized, or if, in the opinion of the Water Resources Commission it shall cause unreasonable obstruction to the free navigation of said waters or endanger the health, safety or welfare of the people of the State, or loss

or destruction of the natural resources of the State, the owner may be ordered by the Commission to remove or alter the structural work, obstructions, or hazards caused thereby without expense to the State; and if, upon the expiration or revocation of this permit, the structure, fill, excavation, or other modification of the watercourse hereby authorized shall not be completed, the owners shall, without expense to the State, and to such extent and in such time and manner as the Water Resources Commission may require, remove all or any portion of the uncompleted structure or fill and restore to its former condition the navigable capacity of the watercourse. No claim shall be made against the State of New York on account of any such removal or alteration.

8. That the State of New York shall in no case be liable for any damage or injury to the structure or work herein authorized which may be caused by or result from future operations undertaken by the State for the conservation or improvement of navigation, or for other purposes, and no claim or right to compensation shall accrue from any such damage.

9. That if the display of lights and signals on any work hereby authorized is not otherwise provided for by law, such lights and signals as may be prescribed by the United States Coast Guard shall be installed and maintained by and at the expense of the owner.

10. All work carried out under this permit shall be performed in accordance with established engineering practice and in a workmanlike manner.

11. This permit shall not be construed as conveying to the applicant any right to trespass upon the lands of others to perform the permitted work or as authorizing the impairment of any right, title or interest in real or personal property held or vested in a person not a party to the permit.

12. Nothing in this permit shall be deemed to affect the responsibility of the permittee to comply with any applicable Rules and Regulations of the U.S. Army Corps of Engineers or any other governmental agency having jurisdiction.

Other Conditions:

13. Make provision for riparian flow to assure downstream owners and water users of an adequate water supply.

The issuance of this permit certifies that it is not contrary to the public interest that the proposed works be done.

The applicant in accepting this permit signifies his agreement to abide by the conditions set forth above.

Application Date August 15, 1966

Expiration Date December 31, 1967

Permit Issued October 3, 1966

By S/ R. A. COOK
Central (Permit Agent)

State Campus Site, Albany, New York 12226
(Name and Address)

cc: J. Gould, Regional Supervisor
A. Dickinson, Dept. of Public Works
Soil Conservation Service, Cooperstown

APPENDIX E
REFERENCES

REFERENCES

1. Chow, Ven Te, Editor - Handbook of Applied Hydrology. McGraw-Hill Book Company, New York, New York, 1964.
2. Hydrologic Engineering Center, U.S. Army Corps of Engineers, HEC-1 Flood Hydrograph Package, Users Manual. Davis, California, January 1973.
3. Hydrologic Engineering Center, U.S. Army Corps of Engineers, Flood Hydrograph Package (HEC-1), Users Manual for Dam Safety Investigations, Davis, California, September 1978.
4. King, Horace and Brater, Ernest. Handbook of Hydraulics, 5th Edition. McGraw-Hill Book Company, New York, New York, 1963.
5. Riedel, J.T., Appleby, J.F. and Schloemer, R.W. Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours (Hydrometeorological Report No. 33) U.S. Department of Commerce - Weather Bureau and U.S. Department of the Army - Corps of Engineers, Washington, D.C., April 1956
6. U.S. Department of the Interior, Bureau of Reclamation, Design of Small Dams, Second Edition, Washington, D.C., 1973.

APPENDIX F

DRAWINGS

LARCHWOOD LAKE

OTSEGO S.&W.C.D.

DRAINAGE AREA
NORMAL POND AREA
POND STORAGE
HEIGHT OF DAM

DESIGNED BY THE
U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

SHEET - 1 COVER SHEET
SHEET - 2 POND AREA
SHEET - 3 POND AREA
SHEET - 4 DAMSITE
SHEET - 5 PROFILES
SHEET - 6 DRAINAGE SYSTEM DETAILS
SHEET - 7 PROFILE OF PRINCIPAL SPILLWAY
SHEET - 8,9,10, RISER STRUCTURAL DETAILS
SHEET - 11 TRASH RACK, & SMALL ANIMAL GUARD
SHEET - 12 COLLAR, CRADLE, BEDDING, BENT, & MINOR
SHEET - 13 POND DRAIN INLET DETAILS
SHEET - 14 LOGS OF TEST HOLES
SHEET - 8A RISER REVISIONS

LARCHWOOD LAKE
SEGO S.&W.C.D.

735 ACRES
59 ACRES
512 AC. FT.
27 FEET

DESIGNED BY THE
DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

SHEET

AREA

AREA

FE

LES

PIPE SYSTEM DETAILS

PIPE OF PRINCIPAL SPILLWAY

STRUCTURAL DETAILS

BRACK, & SMALL ANIMAL. GUARD


CRADLE, BEDDING, BENT, & MISC. DETAILS

RAIN INLET DETAILS

TEST HOLES

REVISIONS

DATE	BY	SHEETS	Y&B	ITEM	APPROVED
REVISIONS					
COVER SHEET					
LARCHWOOD LAKE					
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE					
DESIGNED BY	L. C. BRITTON	DATE	3/66	APPROVED	
BY	M. MULVANEY	DATE	7/66	APPROVED	
BY	MERRILL	DATE	8/66	APPROVED	
				NY-930-P	




EARTH FILL SHALL BE FROM MATERIAL IN SPILLWAY AND SUPPLEMENTAL BORROW ARE BY TP202 FROM 2-8 THE COARSEST MATERIAL PLACED IN THE OUTER MOST PORTION OF THE BY THE ENGINEER

TYPICAL SECTION OF DAM AND FILL PLACEMENT
NOT TO SCALE



BE FROM MATERIAL IN THE EMERGENCY
 SUPPLEMENTAL BORROW AREA REPRESENTED
 2-8 THE COARSEST MATERIAL SHOWN BE
 IN MOST PORTION OF THE DAM AS DIRECTED

- LEGEND**
- DRAINAGE WATER
 - NORMAL WATER LEVEL
 - FLOODING WATER LEVEL
 - CENTER LINE
 - TEST PIT
 - BENCH MARK
 - CREST OF EMERG. SPILLWAY



**LARCHWOOD LAKE
 OTSEGO S & WCD
 POND AREA**


**U. S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE**

Designed by	Date	Approved by
Drawn by	1/10	1/10
Checked by	1/10	1/10
Field notes	1/10	1/10
Scale	1" = 100'	1" = 100'
NY-936-P		

GENERAL NOTES

- 1 AREAS UNDER DAM, DORE, EMERGENCY SPILLWAY, OUTLET CHANNEL AND SUPPLEMENTAL BARRAGE ARE TO BE CLEARED AND GRUBBED LIMITS TO BE CLEARED AND GRUBBED SHALL BE AS STAKED IN THE FIELD BY THE ENGINEER (SPEC 2A)
- 2 ALL CLEARING AND FENCE REMOVAL UPSTREAM FROM DAM WILL BE DONE BY OTHERS
- 3 BOTTOM SECTION OF EMERGENCY SPILLWAY TO BE COVERED WITH 6" OF TOPSOIL ALL ADDITIONAL TOPSOIL THAT IS SUITABLE FOR USE WILL BE INCORPORATED WITHIN THE SLOPES OF THE EARTH FILL AS DIRECTED BY THE ENGINEER







$\Delta = 62^{\circ}08'$ $T = 76.32$
 $R = 130'$ $E = 21.77$
 $D = 44^{\circ}04'$ $M = 10.44$
 $L = 181.0'$

STATION	DEFLECTION	DIST FROM PC
1+30	0	0
1+25	5° 31'	25.00
1+00	11° 01'	41.00
0+75	16° 31'	73.92
0+50	22° 02'	91.53
0+25	27° 32'	120.19
0+00	31° 04'	134.17

LAYOUT NTA - CURVE 1



ELEV. 100' ELEV. 100'



FOR LEGEND SEE SHEET 2

2' CONTOUR INTERVAL

LARCHWOOD LAKE OTSEGO S & WCD DAMSITE	
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
JR MULVANEY	NY-936-P
RM CROWL	
J WILLIAMS	
LB	

120

115

110

105

100

95

90

85

80

0+00


1+00

2+00


3+00

4+00


CONSTRUCTION ELEVATIONS




PROFILE ALONG C OF DAM (LOOKING DOWNSTREAM)



TYPICAL SECTION OF DIKE
(NOT TO SCALE)




TYPICAL SECTION OF CUTOFF TRENCH
(NOT TO SCALE)




SECTION A-A


PRINCIPAL SPILLWAY



PLAN VIEW





SECTION C-C, D-D




DRAINAGE SYSTEM NOTES


ALL DRAIN PIPE SHALL CONFORM TO SPECIFICATION 110 AND SHALL BE 8" DIA. 10 GAUGE, CLASS B HELICAL CORRUGATION SHAPE 1, TYPE A, FULLY BITUMINOUS COATED TO A MINIMUM 40% CORN FILL AROUND PIPES. THE PROFILES OF THE BOTTOM OF ALL EXCAVATIONS AS SHOWN ARE ONLY APPROXIMATE. THE REQUIRED FINISHED GRADES WILL BE ESTABLISHED AT TIME OF CONSTRUCTION BY THE ENGINEER.




SECTION C-C, D-D




PLAN VIEW OF DRAINAGE SYSTEM (EACH SIDE)



LARCHWOOD LAKE OTSEGO S & WCD DRAINAGE SYSTEM DETAILS	
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
No. 1000 L.C. WINTSON Date 7/66 Title W. GRAVIO No. 1000 L. BECK	No. 1000 7/66 No. 1000 8/66 No. 1000 NY-336-P





JOINT	DIST FROM OUTLET	INVERT OF 30" DIA PIPE	SLOPE
OUTLET	0	87.75	—
J-1	16	87.92	0.0087
J-2	32	86.10	0.0087
J-3	48	86.27	0.0087
J-4	64	86.45	0.0087
J-5	80	86.59	0.009
J-6	96	86.69	0.006
J-7	112	86.73	0.003
J-8	120	86.75	0.002



COLLAR	DIST FROM OUTLET	INVERT OF 30" DIA PIPE
10	106	86.72
11	82	86.60
1	58	86.36

30" I.B. REINFORCED WATER PIPE
 (7) 16'-0" SECTIONS
 (8) 8'-0" SECTIONS
 (1) SPIGOT RING WALL FITTING FOR 12" WALL
 TOTAL LENGTH = 121.33'
 PRESSURE HEAD = 25.0'
 LOAD = 24,219 LBS. PER LIN. FT. BASED ON O.D. OF
 30.2" WALL 3 EDGE BEARING STRENGTH FOR 0.001
 CRACK 10,044 LBS. PER LIN. FT. FOR PRESTRESSED PIPE
 (AWWA C-301)



NOTE
ALL RIPRAP SHALL BE WELL
GRADED FROM A MINIMUM SIZE
OF 1" TO A MAXIMUM OF 24" AND
SHALL BE LAID ON 10 FT OF
BEDDING

& OF PRINCIPAL SPILLWAY STA 1+00
AND & OF DAM STA 2+18

SLOPE 2.5:1

& OF PRINCIPAL SPILLWAY

TP 30+0

0 5 10 20 FEET
SCALE

TOP OF SETTLED DAM
ELEV 101

PIPE SUPPLIERS NOTE
CAST OUTSIDE OF SPIGOT RING
WITH CONCRETE ON ONE 16" SECTION

NOTE ALL RIPRAP IN FILLING BASIN
SHALL BE EQUIPMENT PLACED

SECTION A-A

SEVE SIZE	% PASSING
1/2"	100
3/4"	100
1"	100
1 1/2"	100
2"	100
2 1/2"	100
3"	100
3 1/2"	100
4"	100
4 1/2"	100
5"	100
5 1/2"	100
6"	100
6 1/2"	100
7"	100
7 1/2"	100
8"	100
8 1/2"	100
9"	100
9 1/2"	100
10"	100
10 1/2"	100
11"	100
11 1/2"	100
12"	100
12 1/2"	100
13"	100
13 1/2"	100
14"	100
14 1/2"	100
15"	100
15 1/2"	100
16"	100
16 1/2"	100
17"	100
17 1/2"	100
18"	100
18 1/2"	100
19"	100
19 1/2"	100
20"	100
20 1/2"	100
21"	100
21 1/2"	100
22"	100
22 1/2"	100
23"	100
23 1/2"	100
24"	100

NOTE BEDDING SHALL MEET THE
FOLLOWING GRADATION
REQUIREMENTS.

& OF FOUNDATION TRENCH DRAIN

SPIGOT RING JOINT
CAST WITH CONCRETE

ORIGINAL GROUND LINE

INVERT ELEV 85.75

RIAPRAP (SEE NOTE)

ELEV 85.75

OUTLET CHANNEL
SLOPE 0.0025'/ft

& OF BENT
SEE DETAILS SHT 12

SPILLWAY

5 10 FEET


VERTICAL SCALE

11'-6" x 2'-0"


SECTION

TYPICAL SECTION OF OUTLET
CHANNEL EXCAVATION


DATE	7/66	REVISIONS	APP'D
LARCHWOOD LAKE OTSEGO S & WCD PLAN-PROFILE OF PRINCIPAL SPILLWAY			
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE			
Designed by	J.R. MULVANEY	Date	6/66
Drawn by	R.K. CROWE	Date	7/66
Checked by	J. SHERRILL	Date	7/66
Approved by	J.R. MULVANEY	Date	7/66
Project No.		NY-936-P	




PLAN - TOP



SECTION B-B



SECTION A-A



SIDE ELEVATION

For Detail See SHP 12

BAR TYPES

STR

TYPE 1

TYPE 2

SLIDE GATE NOTES

1. 12" DIA SLIDE GATE (SELF CONTAINED TYPE)
2. FLAT FRAME
3. "C" TYPE WALL THIMBLE 8" DEEP
4. SEATING HEAD 10"
5. UNSEATING HEAD 50"
6. OPERATING HEAD 25"
7. NON-RISING STEM THREADED PORTION BRONZE
8. BRONZE LIFT NUTS AND SEAT FACINGS
9. STEM & STEM GUIDES SIZED AND SPACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS

CONSTRUCTION DETAILS

1. BAR DIMENSIONS ARE OUT TO OUT OF BAR
2. RADIUS OF BENDS EQUALS 5 BAR DIAMETER FOR SIZES EQUAL TO OR LESS THAN #7
3. THE 2'-0" 3'-0" DISTANCES FROM SPECIFIED CONCRETE SURFACES ARE CLEAR DISTANCES WHERE SPECIFIED. ALL REINFORCING STEEL PLACED AGAINST THE GROUND SHALL HAVE A MINIMUM OF 2" COVER. ALL REINFORCING STEEL PLACED IN CONCRETE POURED IN FORMS SHALL HAVE A MINIMUM OF 2" CLEAR COVER
4. ALL EXPOSED EDGES OF CONCRETE TO HAVE A 1/4" CHAMFER, UNLESS OTHERWISE NOTED

0 2 4 6 8

SCALE IN FEET

NOTE: BLOCKED IN DIMENSIONS NOT TO SCALE

1/4" x 6" STRUCTURAL CARBON STEEL PLATE GRADE "C" STEEL PLATE IN WALLS TO BE CONTINUOUS AROUND RISER JOINT TO BE WELDED OR BOLTED



RISER CONSTRUCTION JOINT DETAIL


Bar	Qty	Length	Type	B	C	Total Length
1	1	10.0	1			10.0
2	1	10.0	1			10.0
3	1	10.0	1			10.0
4	1	10.0	1			10.0
5	1	10.0	1			10.0
6	1	10.0	1			10.0
7	1	10.0	1			10.0
8	1	10.0	1			10.0
9	1	10.0	1			10.0
10	1	10.0	1			10.0
11	1	10.0	1			10.0
12	1	10.0	1			10.0
13	1	10.0	1			10.0
14	1	10.0	1			10.0
15	1	10.0	1			10.0
16	1	10.0	1			10.0
17	1	10.0	1			10.0
18	1	10.0	1			10.0
19	1	10.0	1			10.0
20	1	10.0	1			10.0
21	1	10.0	1			10.0
22	1	10.0	1			10.0
23	1	10.0	1			10.0
24	1	10.0	1			10.0
25	1	10.0	1			10.0
26	1	10.0	1			10.0
27	1	10.0	1			10.0
28	1	10.0	1			10.0
29	1	10.0	1			10.0
30	1	10.0	1			10.0
31	1	10.0	1			10.0
32	1	10.0	1			10.0
33	1	10.0	1			10.0
34	1	10.0	1			10.0
35	1	10.0	1			10.0
36	1	10.0	1			10.0
37	1	10.0	1			10.0
38	1	10.0	1			10.0
39	1	10.0	1			10.0
40	1	10.0	1			10.0
41	1	10.0	1			10.0
42	1	10.0	1			10.0
43	1	10.0	1			10.0
44	1	10.0	1			10.0
45	1	10.0	1			10.0
46	1	10.0	1			10.0
47	1	10.0	1			10.0
48	1	10.0	1			10.0
49	1	10.0	1			10.0
50	1	10.0	1			10.0
51	1	10.0	1			10.0
52	1	10.0	1			10.0
53	1	10.0	1			10.0
54	1	10.0	1			10.0
55	1	10.0	1			10.0
56	1	10.0	1			10.0
57	1	10.0	1			10.0
58	1	10.0	1			10.0
59	1	10.0	1			10.0
60	1	10.0	1			10.0
61	1	10.0	1			10.0
62	1	10.0	1			10.0
63	1	10.0	1			10.0
64	1	10.0	1			10.0
65	1	10.0	1			10.0
66	1	10.0	1			10.0
67	1	10.0	1			10.0
68	1	10.0	1			10.0
69	1	10.0	1			10.0
70	1	10.0	1			10.0
71	1	10.0	1			10.0
72	1	10.0	1			10.0
73	1	10.0	1			10.0
74	1	10.0	1			10.0
75	1	10.0	1			10.0
76	1	10.0	1			10.0
77	1	10.0	1			10.0
78	1	10.0	1			10.0
79	1	10.0	1			10.0
80	1	10.0	1			10.0
81	1	10.0	1			10.0
82	1	10.0	1			10.0
83	1	10.0	1			10.0
84	1	10.0	1			10.0
85	1	10.0	1			10.0
86	1	10.0	1			10.0
87	1	10.0	1			10.0
88	1	10.0	1			10.0
89	1	10.0	1			10.0
90	1	10.0	1			10.0
91	1	10.0	1			10.0
92	1	10.0	1			10.0
93	1	10.0	1			10.0
94	1	10.0	1			10.0
95	1	10.0	1			10.0
96	1	10.0	1			10.0
97	1	10.0	1			10.0
98	1	10.0	1			10.0
99	1	10.0	1			10.0
100	1	10.0	1			10.0

RISER QUANTITIES


STEEL:				
4 BARS	—	658.83 LIN FT	—	440 LBS
5 BARS	—	1931.16 LIN FT	—	2035 LBS
6 BARS	—	916.25 LIN FT	—	1576 LBS
7 BARS	—	314.60 LIN FT	—	643 LBS
TOTAL	—		—	4494 LBS

CONCRETE (REINFORCED) — 24 CB YDS

JUNE 13 1967	POND DRAIN PIPE	
DATE	ITEM	APP'D
REVISIONS		
LARCHWOOD LAKE		
OTSEGO S & WCD		
RISER STRUCTURAL DETAILS		
U. S. DEPARTMENT OF AGRICULTURE		
SOIL CONSERVATION SERVICE		
Adapted B. ZOGRAFY	5/66	Approved By
W. YOLTON	5/66	By
LS	5/66	NY-938-P



PLAN VIEW OF RISER AT BERM





DETAIL OF RISER AT BERM

STEEL SCHEDULE

MARK	SIZE	QUANTITY	LENGTH	TYPE	B	C	TOTAL LENGTH
R11	#5	20	2-6	1			50-0
R12	#5	6	8-3	1			49-8
R13	#5	6	3-3	1			19-6
R14	#5	20	2-6				50-0
R15	#5	12	8-0	21	2-9	5-3	96-0

NOTE: REFER TO SHEET 10 FOR LOCATION OF REVISED BARS



LARCHWOOD LAKE
OTSEGO S&WCD
RISER REVISIONS

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

J. DE VITA III 9-88


2

Outside Steel Inside Steel

SECTION A-A

0 1 2 3

Scale in Feet




Steel 3" From Bottom of Footing


Steel 2" From Top of Footing

PLAN-FOOTING

AS DIRECTED BY ENGINEER, STEEL IN
SHADED AREA WILL BE CUT, BENT,
OR MOVED AS REQUIRED TO ACCOM-
MODATE POND DRAIN. FOR EXACT
LOCATION OF POND DRAIN SEE SHT. A




Steel 2" from Outside face
UPSTREAM




Steel 2 From Outside face


DOWNSTAIR




Outside Face Steel 2 From Inside Face
UPSTREAM ELEVATION



Steel 2 From Inside Face and 2 From Top of Footing
SIDE WALL ELEVATION




Outside Face Steel 2 From Inside Face
DOWNSTREAM ELEVATION




Steel 2 From Outside Face and 1 From Bottom of Footing
SIDE WALL ELEVATION

3 2 4
Scale in Feet
Unless Otherwise Shown


LARCHWOOD LAKE	
OTSEGO S & WCD	
RISER STRUCTURAL DETAILS	
U. S. DEPARTMENT OF AGRICULTURE	
SOIL CONSERVATION SERVICE	
Drawn by	D. ZOGRAFOS
Scale	5/8"
Sheet	3
Project	NY-916-P




Outside Steel Inside Steel
SECTION A-A
 Scale in Feet



Steel 2" from Outside Face Steel 2" from Inside Face
ENDWALL ELEVATION





Outside Steel Inside Steel
SECTION B-B



Steel 2" from Outside Face Steel 2" from Inside Face


**UPSTREAM & DOWNSTREAM
 ANTI-VORTEX BAFFLE**






0 2 4
Scale in Feet
Unless Otherwise Shown

LARCHWOOD LAKE OTSEGO S & WCD RISER STRUCTURAL DETAILS			
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE			
Designed by D. ZORRABER	Date 5/75	Reviewed by	
Drawn by W. YOLTON	Date 5/66	Checked by	
Project		Sheet	10
Contract L.B.	846	Drawing No.	NY-936-P



2



ALUMINUM GRATING DETAIL



NOTE
ENTIRE TRASH RACK EXCEPT
ALUMINUM GRATING TO BE
PAINTED



RISER TRASH RACK DETAILS
SCALE: 1/4" = 1'-0"

AD-A107 412

FLAHERTY-GIAVARA ASSOCIATES NEW HAVEN CT
NATIONAL DAM SAFETY PROGRAM, LARCHWOOD LAKE DAM (INVENTORY NUMB--ETC(U)
AUG 81 H C FLAHERTY

F/6 13/13

DACW51-81-C-0006

NL

UNCLASSIFIED

3-3

AD-A107 412




END

DATE

FILMED

42-811


DTIC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A


BILL OF MATERIALS

LOCATION	ITEM	SIZE	LENGTH	QUAN
TRASH RACK	5" DIA. PIPE	5" DIA.	8'-4"	10
	3/4" DIA. BOLT	3/4" DIA.	8'-13"	30
	3/4" DIA. NUT	3/4" DIA.	0"	30
	3/4" DIA. WASHER	3/4" DIA.	8'-4" x 3'-9"	1
	GRATING	16" x 2"	3'-9"	3



BOLT DETAIL NO. 1

GRATE IRON, SUPPLY W/ NUTS & WASHERS



SMALL ANIMAL GUARD DETAILS

LARCHWOOD LAKE

OTSEGO S & WCD



TRASH RACK & SMALL ANIMAL GUARD DETAILS

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE


Designed by L. HENYSON	5/56	Approved by S. ANGELO	5/56
Drawn by S. ANGELO	5/56	Checked by L. B.	5/56
NY-936-P		NY-936-P	

1/2" Preformed Joint Filler
18" Wide, Type 1 (Spec. 102)


Symmetrical About C






REINFORCED CONCRETE ANTI-SEEP COLLAR



3 - Req'd.




REINFORCED CONCRETE CRADLE AND BENT DETAILS



POND DRAIN CONCRETE

REINFORCED CONCRETE WATER PIPE JOINT

BAR TYPES



ANTI-SEEP COLLAR STEEL SCHEDULE


Mark	Size	Length	Type	Quan / Letter	Total Quan	Total Length
1-1	4	12	1	4	12	15'-0"
1-2	4	4'-0"	1	8	24	114'-0"
1-3	4	3'-3"	1	8	24	78'-0"
1-4	4	11'-0"	1	4	12	132'-0"
1-5	4	1'-6"	1	4	12	8'-0"
1-6	4	3'-2"	1	8	24	76'-0"

Mark	Section	Quantity	Size	Length	Type	A	B	C	TOTAL	Length
1-1	BENT	16	4	2'-6"	1					40'-0"
1-2		7	6	8'-3"	13	0'-6"	7'-9"	0'-6"	31'-0"	
1-3		6	2	3'-2"	3	0'-0"	0'-0"	0'-0"	12'-0"	
1-4		2	4	4'-3"	1				8'-0"	
1-5		7	2	7'-2"	2	1'-2"	0'-0"	0'-0"	14'-0"	
1-6		2	7	5'-2"	14	1'-6"	0'-0"	1'-6"	10'-0"	


Mark	Section	Quantity	Size	Length	Type	A	B	C	TOTAL	Length
1-1	CRADLE	30	4	8'-7"	12	1'-8"	9'-5"	0'-5"	11'-0"	
1-2		8	9	16'-0"	1				12'-0"	
1-3		4	9	15'-1"	1				60'-0"	
1-4		4	7	15'-6"	1				62'-0"	

CONSTRUCTION NOTES: SEE SHEET E.

CONCRETE BEDDING



OF BENT




1 LAYER OF
44 LBS ROOFING
FELT

SYMMETRICAL ABOUT A

SECTION 44

SECTION 08



TOTAL QUANTITIES COLLARS, CRADLE, BEDDING & BENT

STEEL

2 BARS	35.67	LIN FT	536	LBS
4 BARS	79.33	LIN FT	5310	LBS
6 BARS	33.00	LIN FT	556	LBS
7 BARS	72.32	LIN FT	1878	LBS
9 BARS	128.00	LIN FT	5352	LBS

CONCRETE

REINFORCED	13.52	CU YDS
NON-REINFORCED	8.9	CU YDS


SPIGOT RING WALL FITTING

LARCHWOOD LAKE OTSEGO S & WCD	
COLLAR, CRADLE, BEDDING, BENT & MISC DETAIL	
U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE	
Designed by J. JOGAFOS	Date 5/66
Drawn by J. JOGAFOS	Date 5/66
Checked by J. JOGAFOS	Date 5/66
Project No. 12	Sheet No. 12
Project No. 12	Sheet No. 12


Item	Size	Length	Quan
Angle (A)	$1\frac{1}{2}" \times 1\frac{1}{2}" \times \frac{1}{4}"$	$6' - 11\frac{1}{2}"$	2
Anchor Bolt	$1\frac{1}{2}"$ Dia.	$2' - 9"$	4

Item	Size	Length	Quan
Angle (A)	$1\frac{1}{2}" \times 1\frac{1}{2}" \times \frac{1}{4}"$	$6' - 11\frac{1}{2}"$	2
Anchor Bolt	$1\frac{1}{2}"$ Dia.	$2' - 9"$	4


1 Material in Pond Grain Trash Rack shall conform to Spec II7 for Structural Carbon Steel Plates, Shapes and Bars, Grade C





TRASH RACK




Stainless Steel (Class 303, 303 Se
or 416, Condition A)
*Apply with Hex Nut and Washer




PLAN

**SECTION**

UPSTREAM ELEVATION




SECTION ALONG CENTERLINE



SECTION A

BAR TYPES



POND DRAIN STEEL SCHEDULE

Mark	Qty	Size	Length	Type	B	C	D	Total Length
D-1	3	4	5-9	21	2-2	3-0		20.75
D-2	4	4	9-9	19	6-8	2-9	2-4	37.67
D-3	2	4	8-0	19	6-8	1-4	1-5	16.00
D-4	2	4	8-4	22	3-9	3-10	1-11	16.67
D-5	2	4	5-10	22	1-0	3-10	0-6	11.67
D-6	2	4	2-11	21	2-2	0-9		9.83
D-7	2	4	11-11	22	7-2	4-0	3-7	23.63
D-8	4	4	2-9	1				9.50
D-9	4	4	3-3	1				13.00
D-10	4	4	4-0	1				16.00
D-11	2	4	4-9	1				9.50
D-12	4	4	5-6	21	2-9	2-9		22.00
D-13	4	4	6-2	21	2-9	3-8		24.67
D-14	4	4	5-0	21	2-9	2-3		20.00
D-15	3	4	3-6	1				10.50

QUANTITIES (This Sheet Only)


STEEL

No. 4 Bar 269.1' = 177.1 Lbs.


CONCRETE

Class 4000 3.0 Cu. Yds.


SEE SHEET B FOR CONSTRUCTION DETAILS




SECTION BB



SECTION A A




SECTION C C




LARCHWOOD LAKE OTSEGO S & WCD POND DRAIN INLET DETAILS			
U.S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE			
Designed by L. B.	Date 9/66	Approved by [Signature]	Drawn by [Signature]
Checked by [Signature]	Field Engineer [Signature]	Project Engineer [Signature]	NY-508-P

TP 1	TP 2	TP 3	TP 4	TP 5	TP 101	TP 102	TP 103	TP 104	TP 105	TP 106	TP 107	TP 108	TP 109	TP 110	TP 111	TP 112	TP 113	TP 114	TP 115	TP 116	TP 117	TP 118	TP 119	TP 120	TP 121	TP 122	TP 123	TP 124	TP 125	TP 126	TP 127	TP 128	TP 129	TP 130	TP 131	TP 132	TP 133	TP 134	TP 135	TP 136	TP 137	TP 138	TP 139	TP 140	TP 141	TP 142	TP 143	TP 144	TP 145	TP 146	TP 147	TP 148	TP 149	TP 150	TP 151	TP 152	TP 153	TP 154	TP 155	TP 156	TP 157	TP 158	TP 159	TP 160	TP 161	TP 162	TP 163	TP 164	TP 165	TP 166	TP 167	TP 168	TP 169	TP 170	TP 171	TP 172	TP 173	TP 174	TP 175	TP 176	TP 177	TP 178	TP 179	TP 180	TP 181	TP 182	TP 183	TP 184	TP 185	TP 186	TP 187	TP 188	TP 189	TP 190	TP 191	TP 192	TP 193	TP 194	TP 195	TP 196	TP 197	TP 198	TP 199	TP 200	TP 201	TP 202	TP 203	TP 204	TP 205	TP 206	TP 207	TP 208	TP 209	TP 210	TP 211	TP 212	TP 213	TP 214	TP 215	TP 216	TP 217	TP 218	TP 219	TP 220	TP 221	TP 222	TP 223	TP 224	TP 225	TP 226	TP 227	TP 228	TP 229	TP 230	TP 231	TP 232	TP 233	TP 234	TP 235	TP 236	TP 237	TP 238	TP 239	TP 240	TP 241	TP 242	TP 243	TP 244	TP 245	TP 246	TP 247	TP 248	TP 249	TP 250	TP 251	TP 252	TP 253	TP 254	TP 255	TP 256	TP 257	TP 258	TP 259	TP 260	TP 261	TP 262	TP 263	TP 264	TP 265	TP 266	TP 267	TP 268	TP 269	TP 270	TP 271	TP 272	TP 273	TP 274	TP 275	TP 276	TP 277	TP 278	TP 279	TP 280	TP 281	TP 282	TP 283	TP 284	TP 285	TP 286	TP 287	TP 288	TP 289	TP 290	TP 291	TP 292	TP 293	TP 294	TP 295	TP 296	TP 297	TP 298	TP 299	TP 300	TP 301	TP 302	TP 303	TP 304	TP 305	TP 306	TP 307	TP 308	TP 309	TP 310	TP 311	TP 312	TP 313	TP 314	TP 315	TP 316	TP 317	TP 318	TP 319	TP 320	TP 321	TP 322	TP 323	TP 324	TP 325	TP 326	TP 327	TP 328	TP 329	TP 330	TP 331	TP 332	TP 333	TP 334	TP 335	TP 336	TP 337	TP 338	TP 339	TP 340	TP 341	TP 342	TP 343	TP 344	TP 345	TP 346	TP 347	TP 348	TP 349	TP 350	TP 351	TP 352	TP 353	TP 354	TP 355	TP 356	TP 357	TP 358	TP 359	TP 360	TP 361	TP 362	TP 363	TP 364	TP 365	TP 366	TP 367	TP 368	TP 369	TP 370	TP 371	TP 372	TP 373	TP 374	TP 375	TP 376	TP 377	TP 378	TP 379	TP 380	TP 381	TP 382	TP 383	TP 384	TP 385	TP 386	TP 387	TP 388	TP 389	TP 390	TP 391	TP 392	TP 393	TP 394	TP 395	TP 396	TP 397	TP 398	TP 399	TP 400	TP 401	TP 402	TP 403	TP 404	TP 405	TP 406	TP 407	TP 408	TP 409	TP 410	TP 411	TP 412	TP 413	TP 414	TP 415	TP 416	TP 417	TP 418	TP 419	TP 420	TP 421	TP 422	TP 423	TP 424	TP 425	TP 426	TP 427	TP 428	TP 429	TP 430	TP 431	TP 432	TP 433	TP 434	TP 435	TP 436	TP 437	TP 438	TP 439	TP 440	TP 441	TP 442	TP 443	TP 444	TP 445	TP 446	TP 447	TP 448	TP 449	TP 450	TP 451	TP 452	TP 453	TP 454	TP 455	TP 456	TP 457	TP 458	TP 459	TP 460	TP 461	TP 462	TP 463	TP 464	TP 465	TP 466	TP 467	TP 468	TP 469	TP 470	TP 471	TP 472	TP 473	TP 474	TP 475	TP 476	TP 477	TP 478	TP 479	TP 480	TP 481	TP 482	TP 483	TP 484	TP 485	TP 486	TP 487	TP 488	TP 489	TP 490	TP 491	TP 492	TP 493	TP 494	TP 495	TP 496	TP 497	TP 498	TP 499	TP 500
Topsoil, silty, clay, brown, very fine, (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable, very firm. (G-1) as sub-rounded to blue & small pebbles. Moderately permeable																																																																																																																																																																																																																																																																																																																																																																																																																				

TYPICAL COMPACTION CURVES



COMPACTION CURVE FOR MATERIAL FROM TP 2011, 8'-10' DEEP



COMPACTION CURVE FOR MATERIAL FROM TP 1011, 4'-6' DEEP

UNIFIED SOIL CLASSIFICATION SYMBOLS

- GM Silty gravel; gravel-sand-silt mixtures
- ML Silty clay; v. fine sand; sandy or silty clay
- CL Inorganic clays of low to medium plasticity
- LA - UNIFIED CLASSIFICATION MADE BY VISUAL INSPECTION IN THE FIELD.
- LP - UNIFIED CLASSIFICATION BY THE LABORATORY.

LARCHWOOD LAKE
OTSEGO S & WCD
LOGS OF TEST HOLES

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Investigator	L. KICK	Date	
Approved by	J. R. MULVANEY	Time	
Drawn by		Scale	
NY-936-P			

